



राजस्थान राज्य क्रीडा परिषद

सवाई मानसिंह स्टेडियम, जनपथ, जयपुर

कार्यालय दूरभाष नं० 0141-2744283, फ़ैक्स नं० 0141-2740568, ईमेल आईडी-rsscjaipur@gmail.com

क्रमांक :एफ-8 / त.शा. / ब.घो. 65(XI-4) / 2024-25 / Raj-Kaj Ref. दिनांक : (E-Signed)

निविदा सूचना संख्या 36 / 2026-27

राजस्थान राज्य क्रीडा परिषद, जयपुर की ओर से विद्याधर नगर स्टेडियम-जयपुर के उन्नयन/आधुनिकरण एवं विकास कार्य हेतु राज्य/केन्द्र सरकार के संगठनों/विभागों में पंजीकृत संवेदकों से ई-प्रोक्यूरमेंट प्रक्रिया हेतु ऑनलाइन निविदा आमंत्रित की जाती है।

निविदा से संबंधित अन्य आवश्यक विवरण वेबसाइट <http://sppp.rajasthan.gov.in>, <http://eproc.rajasthan.gov.in> व www.rssc.in पर देखी जा सकती है।

सचिव

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045



M e-Sign



RAJASTHAN STATE SPORTS COUNCIL

TENDER DOCUMENT FOR Upgradation and Mordernisation of Vidhyadhar Nagar Stadium, Jaipur.

NIT NO.	: NIT No. 36/2026-27
ESTIMATED COST	: Rs. 1367.00 Lacs
EARNEST MONEY	: Rs. 27,34,000/-
DATE OF SALE / DOWNLOADING	: From Wednesday August 19, 2026 to Tuesday September 08, 2026 11:00 Hours
DATE OF RECEIPT (D.D. & DOCUMENTS)	: From Wednesday August 19, 2026 to Tuesday September 08, 2026 13:00 Hours
PRE-BID MEETING	: Tuesday September 01, 2026 11:00 Hours
DATE OF OPENING OF TENDER	: Wednesday September 09, 2026 12:00 Hours (Before participating in the pre-bid, the contractor must deposit the tender fee. Only after depositing the tender cost (Not refunded) will the contractor be allowed to participate in the pre-bid)
COMPLETION PERIOD	: 12 Months
COST OF TENDER	: Rs. 5000/- in favour of Secretary, RSSC, Jaipur
PROCESSING FEES	: Rs 2500/- in favour of MD, RISL, Jaipur
DLP Period	: 5 Years

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

Rajasthan State Sports Council. Jaipur

Important Dates of Bids

1. Completion Period	12 Months
2. Date of Issue of Notice Inviting Tender	Wednesday August 19, 2026
3. Period and Places of Sale/ Download of Bidding Documents -	From Wednesday August 19, 2026 to Tuesday September 08, 2026 11:00 Hours http://sppp.rajasthan.gov.in, www.rssc.in & http://eproc.rajasthan.gov.in
4. Deadline for uploading	From Wednesday August 19, 2026 to Tuesday September 08, 2026 11:00 Hours
5. Time and Date for Opening of Bids	Wednesday September 09, 2026 12:00 Hours
6. Place of Opening of Bids	Rajasthan State Sports Council, SMS Stadium, Jaipur-302005
7. Officer Inviting Bids	Secretary, Rajasthan State Sports Council. Jaipur. Address: SMS Stadium, Jaipur-302005
8. Earnest money to be deposited	As per NIT

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

**RajKaj Ref No.:
24126045**

M e-Sign

Instructions and information to bidder regarding Fee, EMD etc.

District	Name of Work Package No.	Estimated Cost (Rs.)	Earnest Money	Time Allowed for completion	End date and time for downloading Tender	Time and date of opening of tender	Place of Sale of documents	Class of contractor.
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Jaipur	Upgradation and Mordernisation of Vidhyadhar Nagar Stadium, Jaipur.	1367.00 Laacs	Rs. 27,34,000/-	12 Months	Tuesday September 08, 2026 11:00 Hours	Wednesday September 09, 2026 12:00 Hours	http://spppp.rajasthan.gov.in , http://eproc.rajasthan.gov.in & www.rssc.in	State/Central के अधिकृत संगठनों के विभागों में पंजीकृत AA Class संवेदक or Eligible Sports Infrastructure Companies

1. The Tender Fee and earnest money as mentioned above should be deposited in the appropriate form as per the tender documents in favour of **Secretary, Rajasthan State Sports Council, Jaipur** payable at **Jaipur** and **Processing Fees** payable at **MD, RISL, Jaipur** payable at Jaipur and must be uploaded scan copy of Registration of Firm, Demand Draft of Tender Cost, Processing Fee & Earnest Money on the site.
2. The tender can be viewed and downloaded from web site <http://spppp.rajasthan.gov.in>, <http://eproc.rajasthan.gov.in> & www.rssc.in.
3. The authorized tender documents are available for inspection in the office of **Rajasthan State Sports Council, SMS Stadium, Jaipur** from all working days.

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

**RajKaj Ref No.:
24126045**

M e-Sign

Annexure A: Compliance with the Code of Integrity and No Conflict of Interest

Any person participating in a procurement process shall-

- (a) Not offer any bribe, reward or gift or any material benefit either directly or indirectly in exchange for an unfair advantage in procurement process or to otherwise influence the procurement process;
- (b) Not misrepresent or omit that misleads or attempts to mislead so as to obtain a financial or other benefit or avoid an obligation;
- (c) Not indulge in any collusion, Bid rigging or anticompetitive behavior to impair the transparency, fairness and progress of the procurement process;
- (d) Not misuse any information shared between the procuring entity and the bidders with an intent to gain unfair advantage in the procurement process;
- (e) Not indulge in any coercion including impairing or harming or threatening to do the same, directly or indirectly, to any party or to its property to influence the procurement process;
- (f) Not obstruct any investigation or audit of a procurement process;
- (g) Disclose conflict of interest, if any; and
- (h) Disclose any previous transgressions with any entity in India or any other country during the last three years or any debarment by any other procuring entity.

Conflict of interest

The Bidder participating in a bidding process must not have a Conflict of Interest.

A Conflict of interest is considered to be a situation in which a party has interests that could improperly influence that party's performance of official duties or responsibilities, contractual obligations, or compliance with applicable laws and regulations.

(i) A bidder may be considered to be in conflict of interest with one or more parties in the bidding process if, including but not limited to:

- (a) Have controlling partners/shareholders in common; or
- (b) Receive or have received any direct or indirect subsidy from any of them; or
- (c) Have the same legal representative for purposes of the bid; or
- (d) have a relationship with each other, directly or through common third parties, that puts them in a position to have access to information about or influence on the bid of another bidder, or influence the decisions of the procuring Entity regarding the bidding process; or
- (e) The bidder participates in more than one bid in a bidding process. Participation by a bidder in more than one bid will result in the disqualification of all bids in which the bidder is involved. However, this does not limit the inclusion of the same subcontractor, not otherwise participating as a bidder, in more than one bid; or
- (f) the bidder or any of its affiliates participated as a consultant in the preparation of the design or technical specifications of the goods, Works or services that are the subject of the Bid; or
- (g) Bidder or any of its affiliates has been hired (or proposed to be hired) by the procuring entity as engineer-in-charge/consultant for the contract.

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

Annexure B: Declaration by the Bidder regarding Qualifications

Declaration by the Bidder

In relation to my/our Bid submitted tofor procurement ofin response to their Notice inviting Bids No.....Dated.....I/wehereby declare under Section 7 of Rajasthan Transparency in Public Procurement Act, 2012 that :

1. I/we possess the necessary professional, technical, financial and managerial resources and competence required by the Bidding Document issued by the Procuring Entry;
2. I/we have fulfilled my/our obligation to pay such of the taxes payable to the union and the state government or any local authority as specified in the Bidding Document.
3. I/we are not insolvent, in receivership, bankrupt or being wound up, not have my/our affairs administered by a court or a judicial officer, not have my/our business activities suspended and not the subject of legal proceedings for any of the foregoing reasons;
4. I/we do not have, and our directors and officers not have, been convicted of any criminal offence related to my/our professional conduct or the making of false statements or misrepresentations as to my/our qualifications to enter into a procurement contract within a period of three years preceding the commencement of this procurement process, or not have been otherwise disqualified pursuant to debarment proceedings;
5. I/we do not have a conflict of interest as specified in the Act, Rules and the Bidding Document, which materially affects fair competition;

Date:
Place:

Signature of bidder
Name:
Designation:
Address:

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

**RajKaj Ref No.:
24126045**

M e-Sign

Annexure C: Grievance Redressed during Procurement Process

The designation and address of the First Appellate Authority is **Joint Secretary**, Youth Affairs & Sports Department Govt. of Rajasthan. The designation and address of the Second Appellate Authority is **Secretary**, Youth Affairs & Sports Department Govt. of Rajasthan, Jaipur.

(1) Filing an appeal:-

if any bidder or prospective bidder is aggrieved that any decision, action or omission of the procuring entity is in contravention to the provisions of the Act or the rules or the guidelines issued there under, he may file an appeal to First Appellate authority, as specified in the Bidding document within a period of ten days from the date of such decision or action, omission, as the case may be, clearly giving the specific ground or grounds on which he feels aggrieved:

Provided that after the declaration of a bidder as successful the appeal may be filed only by a bidder who has participated in procurement proceedings:

Provided further that in case a procuring entity evaluates the technical bids before the opening of the financial bids, an appeal related to the matter of financial bids may be filed only by a bidder whose technical bid is found to be acceptable.

(2) The officer to whom an appeal is filed under Para (1) shall deal with the appeal as expeditiously as possible and shall endeavor to dispose it of within thirty days from the date of the appeal.

(3) If the officer designated under Para (1) fails to dispose of the appeal filed within the period specified in Para (2), or if the bidder or prospective bidder or the procuring entity is aggrieved by the order passed by the first appellate authority, the bidder or prospective bidder or the procuring entity, as the case may be, may file a second appeal to second appellate authority specified in the bidding document in this behalf within fifteen days from the expiry of the period specified in Para (2) or of the date of receipt of the order passed by the first appellate authority, as the case may be.

(4) Appeals not to lie in certain cases:-

No appeal shall lie against any decision of the procuring entity relating to the following matters, namely:-

- (a) Determination of need of procurement
- (b) Provisions limiting participation of bidders in the bid process
- (c) The decision of whether or not to enter into negotiations
- (d) Cancellation of a procurement process
- (e) Applicability of the provisions of confidentiality

(5) Form of Appeals:-

- (a) An appeal under Para (1) or (3) above shall be in the annexed form along with as many copies as there are respondents in the appeal.
- (b) Every appeal shall be accompanied by an order appealed against, if any, Affidavit verifying the facts stated in the appeal and proof of payment of fee,
- (c) Every appeal may be presented to first appellate authority or second Appellate authority, as the case may be, in person or through registered post Or authorized representative.

(6) Fee for filing Appeal:-

- (a) Fee for first appeal shall be rupees two thousand five hundred and for second appeal shall be rupees ten thousand, which shall be non-refundable.
- (b) The fee shall be paid in the form of bank demand draft or banker's cheque of a scheduled bank in India payable in the name of appellate authority concerned.

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 11:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

(7) Procedure for disposal of Appeal:-

- (a) The first appellate authority or second appellate authority as the case may be, upon filing of appeal, shall issue notice accompanied by copy of appeal, affidavit and documents, if any, to the respondents and fix date of hearing
- (b) On the date fixed for hearing, the first appellate authority or second appellate authority, as the case may be shall-
 - (i) Hear all the parties to appeal present before him; and
 - (ii) Peruse or inspect documents, relevant records or copies thereof relating to the matter.
- (c) After hearing the parties, perusal or inspection of documents and relevant records or copies thereof relating to the matter, the appellate authority concerned shall pass an order in writing and provide the copy of order to the parties to appeal free of cost.
- (d) The order passed under sub-clause (c) above shall also be placed on the state public procurement portal.

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

**RajKaj Ref No.:
24126045**

M e-Sign

Annexure D: Additional Conditions of Contract

1. Correction of arithmetical errors

Provided that a Financial Bid is substantially responsive, the Procuring Entity will correct arithmetical errors during evaluation of Financial Bids on the following basis:

- i. If there is a discrepancy between the unit price and the total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail and the total price shall be corrected, unless in the opinion of the Procuring Entity there is an obvious misplacement of the decimal point in the unit price, in which case the total price as quoted shall govern and the unit price shall be corrected;
- ii. If there is an error in a total corresponding to the addition or subtraction of subtotals, the subtotals shall prevail and the total shall be corrected; and
- iii. If there is a discrepancy between words and figures, the amount in words shall prevail, unless the amount expressed in words is related to an arithmetic error, in which case the amount in figures shall prevail subject to (i) and (ii) above.

If the Bidder that submitted the lowest evaluated Bid does not accept the correction of errors, its Bid shall be disqualified and its Bid Security shall be forfeited or its Bid Securing Declaration shall be executed.

2. Procuring Entity's Right to Vary Quantities

- (i) At the time of award of contract, the quantity of Goods, Works or services originally specified in the Bidding Document may be increased or decreased by a specified percentage, but such increase or decrease shall not exceed Five percent, of the quantity specified in the Bidding Document. It shall be without any change in the unit prices or other terms and conditions of the Bid and the conditions of contract.
- (ii) If the Procuring Entity does not procure any subject matter of procurement or procures less than the quantity specified in the Bidding Document due to change in circumstances, the Bidder shall not be entitled for any claim or compensation except otherwise provided in the Conditions of Contract.
- (iii) In case of procurement of Goods or services, additional quantity may be procured by placing a repeat order on the rates and conditions of the original order. However, the additional quantity shall not be more than 50% of the value of Goods of the original contract and shall be within one month from the date of expiry of last supply. If the supplier fails to do so, the Procuring Entity shall be free to arrange for the balance supply by limited Bidding or otherwise and the extra cost incurred shall be recovered from the supplier.

3. Dividing quantities among more than one Bidder at the time of award (In case of procurement of Goods)

As a general rule all the quantities of the subject matter of procurement shall be procured from the Bidder, whose Bid is accepted. However, when it is considered that the quantity of the subject matter of procurement to be procured is very large and it may not be in the capacity of the Bidder, whose Bid is accepted, to deliver the entire quantity or when it is considered that the subject matter of procurement to be procured is of critical and vital nature, in such cases, the quantity may be divided between the Bidder, whose Bid is accepted and the second lowest Bidder or even more Bidders in that order, in a fair, transparent and equitable manner at the rates of the Bidder, whose Bid is accepted.

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

**RajKaj Ref No.:
24126045**

M e-Sign

राजस्थान राज्य क्रीडा परिषद

सवाई मानसिंह स्टेडियम, जनपथ, जयपुर

कार्यालय दूरभाष नं० 0141-2744283, फ़ैक्स नं० 0141-2740568, ईमेल आईडी-rsscjaipur@gmail.com

बोली की शर्तें

विशेष टिप्पणी :- बोलीदाताओं को इन शर्तों को सावधानी पूर्वक पढ़ना चाहिए तथा अपनी ई-बोलियां भेजते समय इनकी पूर्ण रूपेण पालना करनी चाहिए।

1. तकनीकी प्रस्तावों में सफल बोलीदाताओं के ही वित्तीय प्रस्ताव खोले जावेंगे जो निविदादाता तकनीकी बिड में सफल नहीं पाये गये उनकी वित्तीय बोली नहीं खोली जायेगी।
2. कोई भी फर्म/संवेदक यदि जी.एस.टी. अधिनियम के अन्तर्गत पंजीकृत नहीं है तो वह बोली नहीं देगा। इनके अभाव में बोलियों पर विचार नहीं किया जायेगा। जी. एस. टी. देयता प्रमाण पत्र मार्च, 2026 का संलग्न करना आवश्यक है।
3. दरें जी.एस.टी. तथा केन्द्र व राज्य सरकार द्वारा देय समस्त करों सहित देनी होगी।
4. बोली ऑन-लाईन प्रस्तुत की जावेगी एवं निर्दिष्ट कॉलमों में प्रविष्टि की जावेगी।
5. दरें गन्तव्य स्थान तक एफ.ओ.आर. सवाई मानसिंह स्टेडियम जयपुर के आधार पर होगीं अर्थात् परिवहन संबंधी कोई राशि परिषद द्वारा पृथक से देय नहीं होगी।
6. बोलियां उपापन अधिनियम/पारदर्शिता अधिनियम के तत्संबंधी प्रावधानों (धारा-28 आदि) के अध्वधीन रहते हुये उनके खोले जाने की दिनांक से एक वर्ष की अवधि के लिए विधि मान्य होंगी।
7. बोलीदाता अपनी संविदा या उसके किसी भाग को किसी अन्य एजेन्सी के लिए नहीं सौंपेगा या उपभाडे पर नहीं देगा।
8. बोलीदाता का उसके प्रतिनिधि की ओर से प्रत्यक्ष अथवा अप्रत्यक्ष रूप से अपना पक्ष समर्थन करना एक प्रकार की अनर्हता होगी। हित विरोधी धारा 80 होगी।
9. विहित समय एवं तारीख के पश्चात् जो भी बोलियां प्राप्त होंगी उन्हें किसी स्थिति में स्वीकार नहीं किया जावेगा।
10. यदि बोलीदाता ऐसी कोई शर्त आरोपित करता है जो उसमें वर्णित शर्तों के अतिरिक्त है या उनके विरोध में है तो उसकी बोली को संक्षिप्त रूप में कार्यवाही कर रद्द कर दिया जावेगा।
11. तकनीकी बोली के साथ बोलीदाता को निम्न दस्तावेज संलग्न करने अनिवार्य होंगे (जिसके आधार पर तकनीकी बिड का मूल्यांकन किया जायेगा) :-
 - i. बोली में अंकित पते के प्रमाण हेतु पानी/बिजली/टेलीफोन/मोबाईल के बिल, पेन कार्ड, पासपोर्ट, आधार कार्ड अथवा ड्राईविंग लाईसेन्स में से कोई एक की प्रमाणित छाया प्रतियां।
 - i. बोलीदाता/फर्म का विगत 5 वित्तीय वर्षों (2021-22, 2022-23, 2023-24, 2024-25 एवं 2025-26) में औसत वार्षिक टर्न ओवर 1367.00 लाख से कम नहीं होना चाहिये। इस हेतु बोलीदाता को उक्त वर्षों का सीए से प्रमाणित प्रमाण पत्र की प्रति मय यूडीआई नम्बर सहित संलग्न करनी होगी।

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 14:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

- ii. गत 5 वर्षों (2021-22 से 2025-26) में एक ओलम्पिक/सेमी ओलम्पिक साईज स्वीमिंग पूल, एक वाकिंग/सिन्थेटिक ट्रैक से संबंधित निर्माण कार्य का अनुभव होना आवश्यक है, इसके प्रमाणीकरण हेतु कार्यादेश एवं कार्य के सन्तोषजनक होने का प्रमाण पत्र आदि आवश्यक दस्तावेज संलग्न करने होंगे।
- iii. बोलीदाता को माल एवं सेवाकर (GST) के रजिस्ट्रेशन की प्रति संलग्न करनी होगी।
- iv. अमानत राशि एवं बोली प्रपत्र शुल्क का डी.डी. संलग्न करना होगा।

12. बयाना राशि :-

- (क) बोली से पूर्व (2%) नियमानुसार बयाना राशि ऑफ-लाईन प्रस्तुत की जायेगी। इसके बिना बोलीओं पर विचार नहीं किया जायेगा। यह राशि सचिव, राजस्थान राज्य क्रीड़ा परिषद, जयपुर के पक्ष में बैंक ड्राफ्ट/बैंकर्स चैक में से किसी रूप में जमा करायी जा सकती है।
- (ख) असफल बोलीदाता की बयाना राशि बोली को अंतिम रूप से स्वीकार करने के बाद यथा संभव शीघ्र लौटा दी जावेगी।
- (ग) अनुमोदन की प्रतीक्षा करने वाली या रद्द की गई या संविदाओं के पूर्ण हो जाने के कारण परिषद कार्यालय के पास जमा बयानाराशि/प्रतिभूति निक्षेप को नवीन निविदा के लिए बायाना राशि/प्रतिभूति राशि के प्रति समायोजित नहीं किया जायेगा।

13. बयाना राशि का समपहरण:- बयाना राशि को निम्नलिखित मामलों में समपहरत कर लिया जायेगा:-

- (क) जब बोलीदाता बोली खोलने के बाद किन्तु बोली को स्वीकार करने के पूर्व प्रस्ताव को वापस लेता है या उसमें उपान्तरण करता है।
- (ख) जब बोलीदाता विनिर्दिष्ट समय के भीतर विहित करार को निष्पादित नहीं करता है।
- (ग) जब बोलीदाता प्रदायगी के लिए आदेश देने के बाद प्रतिभूति राशि जमा नहीं कराता हो।
- (घ) जब वह निर्धारित समय के अन्तर्गत आदेशों के अनुसार कार्य करने में असफल रहता है अथवा संतोषजनक सेवाएं देने में असमर्थ रहता है।

14. करार एवं प्रतिभूति निक्षेप :-

- (क) सफल बोलीदाता को आदेश दिनांक से 7 दिन की अवधि के भीतर नियमानुसार मूल्य के नॉन ज्यूडिशियन स्टॉम्प पेपर पर (जिसका व्यय स्वयं बोलीदाता द्वारा वहन किया जावेगा) एक करार-पत्र निष्पादित करना होगा तथा प्रावधित मूल्य जिसके लिए बोली स्वीकार की गई है।
- (ख) बोली के समय जमा कराई गई बयाना राशि को प्रतिभूति की राशि के लिए समायोजित किया जायेगा।
- (ग) बयाना/प्रतिभूति राशि पर परिषद द्वारा कोई ब्याज का भुगतान नहीं किया जायेगा।
- (घ) प्रतिभूति राशि के रूप में नकद रसीद पत्र/शिड्यूल बैंक का ड्राफ्ट/बैंकर्स चैक मान्य होंगे।

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

15. **प्रतिभूति राशि का समपहरण** :- प्रतिभूति की राशि को पूर्ण अथवा आंशिक रूप से निम्नलिखित मामलों में समपहरत किया जायेगा:-
- (क) जब संविदा की किसी शर्त/अथवा शर्तों का उल्लंघन किया गया हो।
 - (ख) जब बोलीदाता सम्पूर्ण कार्य संतोषजनक ढंग से करने में असफल रहा हो।
 - (ग) प्रतिभूति निक्षेप को समपहरत करने के मामले में युक्तियुक्त नोटिस दिया जावेगा इस सम्बन्ध में परिषद के अधिकारी का निर्णय अन्तिम होगा।
 - (घ) कार्य में असफल रहने पर परिषद द्वारा वैकल्पिक व्यवस्था किये जाने पर उसमें जो भी व्यय होगा बोलीदाता से उसकी प्रतिभूति राशि में से अथवा उसको देय बिल की राशि के भुगतान में से की जायेगी। यदि वसूली करना सम्भव न हो तो राजस्थान पी.डी.आर.एक्ट या प्रवृत्त अन्य किसी कानून के अन्तर्गत कार्यवाही की जावेगी।
16. करार पत्र को पूर्ण करने एवं उस पर स्टाम्प लगाने का व्यय बोलीदाता द्वारा वहन किया जायेगा तथा परिषद को उस करार पत्र की निष्पादित स्टाम्प शुदा प्रति पडत निःशुल्क प्रस्तुत की जायेगी।
17. परिषद के प्राधिकृत अधिकारी या उसका विधिवत् प्राधिकृत प्रतिनिधि सभी युक्तियुक्त उचित समयों पर ठेकेदार के परिसर में जायेगा तथा वह विनिर्माण की प्रक्रिया के दौरान या उसके बाद जैसे भी हो किसी भी समय सामग्री का निरीक्षण एवं जांच करने की शक्ति रखेगा।
18. परीक्षण प्रभार परिषद द्वारा वहन किये जायेंगे। यदि बोलीदाता अत्यावश्यक तत्काल परीक्षण कराना चाहता है या यदि परिणामों से यह ज्ञात होता है कि प्रदाय किया गया सामान विहित स्तरों या विनिर्देशों के अनुसार नहीं है तो परीक्षण प्रभार बोलीदाता द्वारा वहन किये जायेंगे।
19. अनुमोदित कार्य के लिए यह समझा जाएगा कि उसने कार्य किये जाने वाले विनिर्देशों की सावधानीपूर्वक जांच कर ली है यदि उसे इन शर्तों, विनिर्देशों, रेखाचित्रों आदि के किसी भाग के आशय के बारे में कोई सन्देह हो तो वह संविदा पर हस्ताक्षर करने से पूर्व परिषद से स्पष्टीकरण प्राप्त करेगा।
20. सफल बोलीदाता को कार्य आदेश जारी तिथि के 10 दिवस के अन्दर कार्य प्रारम्भ करना होगा।
21. यदि निविदा सूचना में दर्शित मात्रा से अधिक के लिए आदेश दिया जाता है, तो निविदादाता अपेक्षित कार्य करने के लिए बाध्य होगा। पुनः आदेश भी निविदा में दी गयी शर्तों पर दिए जा सकेंगे परन्तु शर्त यह है, कि ऐसे पुनःआदेश मूल रूप से खरीदी गयी मात्रा की 50 प्रतिशत तक के अतिरिक्त प्रदाय के लिए ही होंगे।
22. **गारन्टी** :- गारन्टी अवधि 5 वर्ष होगी।
23. **परिसमापित नुकसानी** :-
- (1) परिसमापित नुकसानी के साथ कार्य अवधि में वृद्धि करने के मामले में, वसूली राजस्थान लोक उपापन पारदर्शिता अधिनियम, 2012 एवं राजस्थान लोक उपापन पारदर्शिता नियम 2013 के प्रावधान अनुसार होगी।
 - (2) यदि प्रदायकर्ता किन्हीं बाधाओं के कारण संविदान्तर्गत कार्य का प्रदाय पूरा करने के लिए समय में वृद्धि कराना चाहता है, तो वह लिखित में परिषद को आवेदन करेगा। किन्तु वह उसके लिए निवेदन बाधा के घटित होने पर तुरन्त उसी समय करेगा न कि प्रदाय पूर्ण होने की निर्धारित तारीख के बाद करेगा।

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

(3) यदि कार्य प्रदाय करने में उत्पन्न हुई बाधा बोलीदाता के नियन्त्रण से परे कारणों से हुई हो तो कार्य की अवधि में वृद्धि परिसमापित नुकसानी सहित या रहित की जा सकेगी।

24. **वसूली** :-परिसमापित नुकसानी, कम प्रदाय, टूट-फूट, रद्द की गई वस्तुओं के लिए वसूली साधारण रूप से बिल में से की जाएगी। संवेदक कम प्रदाय, टूट-फूट, रद्द किए गए कार्यों की सीमा तक राशि को भी रोका जा सकेगा तथा यदि सेवा सन्तोषजनक ढंग से उनको कार्य करता है तो परिसमापित नुकसानी के साथ वसूली उसे देय राशि एवं विभाग के पास उपलब्ध प्रतिभूति निक्षेप से की जाएगी। यदि वसूली करना सम्भव न हो तो राजस्थान पी डी आर एक्ट या प्रवृत्त अन्य कानून के अन्तर्गत कार्रवाई की जाएगी।

25. भुगतान :-

(क) बोलीदाता द्वारा क्रेता अधिकारी को उचित प्रारूप में लोक उपापन नियमों के अनुसार बिल प्रस्तुत करने पर भुगतान किया जायेगा। सभी प्रेषण प्रभार बोलीदाता द्वारा वहन किये जायेंगे। किसी भी सूरत में अग्रिम भुगतान नहीं किया जायेगा।

(ख) विवादास्पद मदों में राशि का 10 प्रतिशत से 25 प्रतिशत तक को रोका जायेगा तथा उस विवाद का निपटारा हो जाने पर उसका भुगतान कर दिया जायेगा।

(ग) उन मामलों में, जिनमें परीक्षण करने की जरूरत है, भुगतान तभी किया जायेगा जब उनका परीक्षण कर लिया जाये तथा प्राप्त हुए परीक्षण परिणाम विहित निर्देशों के अनुरूप हों।

26. यदि कार्य की तात्कालिक आवश्यकता के कारण पूर्ण या आंशिक रूप में उन कार्यों को बदलना साध्य नहीं समझा जाए तो राजस्थान राज्य क्रीडा परिषद द्वारा बोलीदाता को सुनवाई किये जाने का एक उचित अवसर देकर, ऐसे कारणों से जो अभिलिखित किये जायेंगे, अनुमोदित दरों में से उपयुक्त राशि की कटौती करेगा। इस प्रकार की गई कटौती अन्तिम होगी।

27. निविदादाता करार को निष्पादित करते समय निम्नलिखित दस्तावेज प्रस्तुत करेगा :-

(i) यदि भागीदारी फर्म हो तो "पार्टनरशिप डीड" की अनुप्रमाणित प्रति।

(ii) यदि भागीदारी फर्म रजिस्ट्रार ऑन फर्म्स के पास पंजीकृत हो तो पंजीयन संख्या एवं उसका वर्ष।

(iii) एक मात्र स्वामित्व के मामले में आवास एवं कार्यालय का पता, टेलीफोन नम्बर।

(iv) कम्पनी के मामले में कम्पनी के रजिस्ट्रार के द्वारा जारी किया गया प्रमाण-पत्र।

28. संविदा के निर्वचन, आशय या संविदा की शर्तों के उल्लंघन के सम्बन्ध में या अन्य किसी भी प्रकार का विवाद होने पर परिषद का निर्णय अन्तिम होगा।

29. समस्त विधिक कार्यवाहियां यदि संस्थित किया जाना आवश्यक हो तो जयपुर स्थित न्यायालय में ही की जाएगी। अन्यत्र नहीं की जाएगी।

30. बोलीदाता द्वारा अपलोड किये जाने वाले दस्तावेजों पर नम्बरिंग होनी चाही एवं चैक लिस्ट भर कर प्रस्तुत करनी होगी।

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

31. सचिव, राजस्थान राज्य क्रीडा परिषद, जयपुर को बिना कारण बताये किसी भी बोली को स्वीकार/अस्वीकार करने का अधिकार होगा।
32. परियोजना में उपयोग में लिये जाने वाले आईटमों की दरें एवं यूनिट सानिवि की भवन बीएसआर-2022 विद्युत बीएसआर-2022 एवं सडक बीएसआर-2025 पर आधारित है। सभी दरों में किसी प्रकार की त्रुटि उक्त बीएसआर दरों से संशोधित मानी जावेगी।
33. जी.एफ. एण्ड ए.आर., राजस्थान लोक उपापन पारदर्शिता अधिनियम, 2012 एवं राजस्थान लोक उपापन पारदर्शिता नियम 2013 के प्रावधान लागू होंगे।
34. **Special Conditions of Contract:**
 1. Jogging Track product should be of European, Australian, American Origin only. Manufacturer's declaration should be submitted with technical bid.
 2. Joint ventures and consortium are not accepted.
 3. The Manufacturer should be an OEM for the bidder for the product being proposed. Manufacturer to give an undertaking of exclusivity for the said project to the bidder.
 4. The Engineer-in-Charge / Rajasthan State Sports Council shall have the full and exclusive right to require testing of any material, at any stage and prior to final acceptance, in laboratories of their choice, including approved laboratories. The bidder/contractor shall, at his own cost, make all necessary arrangements for such testing (except those specified elsewhere in the tender documents) and shall bear all expenses towards sampling, testing, packing, transportation, loading, unloading and all incidental charges whatsoever. Any material found not conforming to the prescribed specifications, standards or quality requirements shall be rejected and shall not be accepted for use in the work.
 5. Contractor Must Established quality control lab at site.
 6. In case any material/work is found substandard the same shall be rejected by the Engineer-in-Charge and the same shall be removed from the site of work within 48 hours, failing which the same shall be got removed by the Engineer-in-Charge at the risk & cost of the Contractor without giving any further notice and time.
 7. The Bidder shall ensure quality control measures on different aspects of construction including materials, workmanship and correct construction methodologies to be adopted.
 8. The Malba/Garbage generated at site due to construction activities shall be removed from the site immediately & shall be disposed off by the contractor to the approved dumping site from local bodies shall be a sole responsibility of contractor.
 9. The contractor shall make his own arrangement to get permission with respect to trucks from the Traffic Police.
 10. The bidder should not blacklisted or debarred by any Central Government department, State Government department, Public Sector undertaking in India.
 11. The contractor must provide vehicle for inspection of project site as an when required by Engineer-In-Charge.
 12. Contractor must provide own cost Supervisor (Maximum pay Rs. 16500) advised by RSSC Engineer In-Charge. No Additional payment done by RSSC.

**बोलीदाता के हस्ताक्षर
(मय नाम पता एवं मोहर)**

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

**RajKaj Ref No.:
24126045**

M e-Sign

घोषणा

मैंने/हमने राजस्थान राज्य क्रीडा परिषद, जयपुर की ओर से विद्याधर नगर स्टेडियम—जयपुर के उन्नयन/आधुनिकरण एवं विकास कार्य हेतु (मय सामग्री) की बोली के नियम एवं शर्तों को भली-भाँति पढ़ व समझ लिया है। मुझे/हमारी फर्म को किसी भी विभाग द्वारा ब्लैक—लिस्ट नहीं किया गया है। इन शर्तों एवं नियमों के अधीन मैं/हम उक्त निर्माण कार्य करने हेतु सहमत एवं वचनबद्ध हूँ/हैं। यदि मेरे/हमारे द्वारा की किसी बोली की शर्तों, नियमों अथवा आदेशों का उल्लंघन किया जावेगा तो सक्षम अधिकारी द्वारा मेरे/हमारे विरुद्ध बोली के नियम/शर्तों के उल्लंघन की कार्यवाही करने के लिए अधिकृत होगा। इस सम्बन्ध में मुझे/हमें सक्षम/अधिकृत अधिकारी द्वारा लिया गया निर्णय मान्य होगा तथा इसमें मुझे/हमको कोई आपत्ति/हस्तक्षेप नहीं है।

हस्ताक्षर बोलीदाता.....

नाम/पता

टेलीफोन नं.

दिनांक

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

General Instructions for Filling of Bid

The complete bidding document has been published on the website www.rssc.in, <http://sppp.raj.nic.in>, <http://eproc.raj.gov.in>, for the purpose of downloading.

1. Bidders who wish to participate in this bidding process must register on www.rssc.in & <http://sppp.raj.nic.in>,
2. To participate in online bidding process, Bidders must procure a Digital Signature Certificate (Type III) as per Information Technology Act-2000 using which they can digitally sign their electronic bids. Bidders can procure the same from any CCA approved certifying agency, i.e. TCS, safe crypt, Node etc. Bidders who already have a valid Digital Signature Certificate (DSC) need not procure a new DSC.
3. Bidder (authorized signatory) shall submit their offer on-line in electronic formats both for Technical and financial proposal. However, DD for Tender Fees, EMD payable in favor of SECRETARY RAJASTHAN STATE SPORTS COUNCIL, JAIPUR, payable at Jaipur and Processing Fees payable in favor of Managing Director, RAJCOMP Info Services Limited, payable at JAIPUR. **Tender fee, EMD and processing fee DD should be submitted physically at the office of RAJASTHAN STATE SPORTS COUNCIL, JAIPUR, and Scanned copy of same should also be uploaded along with the technical bid.**
4. RAJASTHAN STATE SPORTS COUNCIL, JAIPUR will not be responsible for delay in online submission due to any reason. For this, bidders are requested to upload the complete bid well advance in time so as to avoid Last hours issues like slow speed; choking of web site due to heavy load or any other unforeseen problems.
5. Bidders are also advised to refer "Bidders Manual Kit" available at e-Proc website for further details about the e-tendering process.
6. No contractual obligation, whatsoever shall arise from the bidding process unless and until a formal contract is signed and executed between the tendering authority and the successful Bidder.

SECRETARY

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

UNDERTAKING BY THE BIDDER

This is to certify that I/we before signing this tender have read and fully understood all the terms and conditions contained herein and undertake myself/ourselves to abide by them. I/We have signed all the pages in acceptance of the terms and conditions.

I/We also undertake that I/We will not adopt any malpractices at any stage of bidding/execution.

Signature of the Bidder with Seal

Name:

Designation:

Address:

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

BIDDER'S AUTHORIZATION CERTIFICATE {to be filled by the bidder}

To,
{Tendering Authority},

_____,

I/
We.....{Name/Designatio
n} hereby declare/ certify that
.....

..... {Name/ Designation} is hereby authorized to sign
relevant documents on behalf of the company/ firm in dealing with Tender with
RAJASTHAN STATE SPORTS COUNCIL, JAIPUR.

He/ She is also authorized to attend meetings & submit technical & commercial
information/ clarifications as may be required by you in the course of processing the Bid.
For the purpose of validation, his/ her verified signatures are as under.

Thanking you,

Name of the Bidder: -
Authorized Signatory: -
Seal of the Organization: -
Date:
Place:

Verified Signature:

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

CHECKLIST OF DOCUMENTS SUBMITTED

S. No.	Documents to be submitted	Submitted	Not Submitted	Page No.
1.	Scanned Copies of tender document fee, EMD and processing fees			
2.	Copy of Registration of firms.			
3.	Copy of GST Registration			
4.	Copy of PAN Card			
5.	Proof of Work order and Satisfactory Completion of work should be as per tender document condition no. 11 (iii) in financial Year 2021-22 to 2025-26.			
6.	Certificate from Chartered Accountant having UDIN for the proof of average annual Turnover that must be equal/more than the cost of work (bid cost) in the last Five Financial Years from 2021-22 to 2025-26			
7.	Annexure A to D duly signed in context to RTPP Rules-2013.			
8.	Authorization certificate If the tender is signed other than owners			
9.	Copy of GST paid certificate filed by March, 2026 Financial Year 2025-26 in GSTR-3B Performa			
10.	Tender document and Technical Bid and undertaking all three duly signed			
11.	Any other Document			

Note: -

1. Work means the work executed under Public Sector/Autonomous Bodies/ Development Authority/Municipal Corporation of Central/State Government.
2. The contractor should ensure that the Registration should be latest or updated.

Signature of Bidder Seal of Establishment
Full Name of Bidder with address and
date

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

PART-B (FINANCIAL BID)**Bill of Quantities**

NAME OF WORK :- Upgradation and Mordernisation of Vidhyadhar Nagar Stadium, Jaipur

S. No.	Quantity	Particular	Rate (Including All Taxes)	Unit	Amount
A		Walking Track			
1	2520.00	Supply and installation of Cast in situ IAAF approved Synthetic Athletics SANDWICH track system with minimum 14.1mm thick.The system consumption ratios consist of application of primer layer of 0.15 kg/sqm, 10mm thick shock pad base layer of SBR granules (1-4mm) with 6.5kg/sqm mixed with PU binder 1.2 kg/sqm, Pore sealing PU layer over laid shock pad @ 1.2kg/sqm, then top wear coat of liquid PU with consumption of 2.20 kg/sqm and EPDM granules of 1-3.5mm broadcasted in the range of 2.8 kg/sqm		Sqm	
B		Covering of Sitting Tiers			
2	1955.00	Design, Fabrication, Manufacturing, Assembly, Supply & installation of 750gsm tensile membrane with Fabric of serge Ferrari or approved equivalent with standard specification and warranty of the manufacturer with Supporting Galvanized steel wire ropes/cables, MS frame work (including painting etc. complete) as per design and direction of engineer-in-charge, fittings as required for connecting to existing RCC columns/beams or walls/ on all four sides with necessary fixing arrangement like dash fasteners, clamps etc including scaffolding complete as per directions of Engineer-In-Charge. Note: The roofing system is to be designed and executed in such a way that it will have proper airtight joints with metal and other surfaces so that the structure is water tight. The Fabric structure above all the main support shall be in off white Color. The fabric shall be high quality 750 gsm multi layer PTFE coated Glass fiber finish and PTFE alloy finish to the bottom surface. The rates includes cost of design of system (MS frame structure etc complete). Supply and installation of Fabric, Galvanized Steel wire ropes/cables, Accessories, perimeter attachment systems, Fabrication of Membrane and connection systems, Member of MS frame PTFE maintenance kit, erection and dismantlement of required scaffolding, Membrane and Connection system & tensioning and working at all levels, leads and heights complete as per the drawings & particular specifications and directions of Engineer-in-Charge. The plan area covered by the tensioned fabric will be measured for payment.		Sqm	
C		Swimming Pool			
1	1688.25	Providing & Fixing approved brand tiles of size 100mm X 100 mm Porcelain Mosaic tiles with thickness of 8mm of 0.032% water observation general chemical acid resistant fixing by MYK Laticrete/ JK CEMENT/ Kerakoll/ MAPEI make 252 Ag.Silver mosaic adhesive fixing by fina specification or as per standard lane marking of swimming pool complete as directed by engineer in charges . Italia, Piccolo, Keramika, Onix with epoxy based grouting of MYK Laticrete, JK CEMENT, Kerakoll, MAPEI etc.		Sqm	

Signature validDigitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: ApprovedRajKaj Ref No.:
24126045

M e-Sign

2	1813.25	Providing and Applying water proofing treatment to pool basin, overflow channel and balancing tank with one layer primer coat & 2 layer coating of 2-component acrylic polymer based water proofing compound. In addition, Micro-concrete repair, injection grouting & fibre mesh fixing wherever necessary shall be part of waterproofing treatment (Nerolac Perma, Pidilite, Dr.Fixit, Myk Arment, Laticrete)		Sqm	
3	1112.10	Providing and laying ANTI SKID designer floor tiles for deck area (Simpolo/Larson/Pavit/eqv.) thickness to be specified by the manufacturer of 1st quality conforming to IS 15622 of approved make in colours shade except white ivory grey fume red, brown laid on 20mm thick cement mortar 1:4 (1 cement : 4 sand)		Sqm	
4	4.00	Filtered Water Piping Supply, Installation & Commissioning of delivery PVC Piping from filter room to swimming pool inlet 110 mm/6 Kg pipe size from Filter Room up to the Bottom Distribution piping inside the swimming pool complete with elbows, pipe ends and fittings etc. complete		set	
5	4.00	Bottom Distribution Piping Supply, Installation & Commissioning of PVC Bottom Distribution Piping in 110 mm/ 6 Kg pressure pipe with Nozzles connectors in the swimming pool complete and all allied interconnecting fittings etc.		set	
6	2.00	Over Flow Piping Supply, Installation & Commissioning of OVER FLOW Piping in PVC Pipe 315 mm/ 2.5 Kg from swimming pool over flow channel & up to the balancing tank		set	
7	2.00	Drain Piping Supply, Installation & Commissioning of Drain Piping in PVC 110 mm/6 kg size from Main Drain inside the swimming pool & up to the balancing tank bottom complete with valve & fittings		set	
8	4.00	Supply, Instalation, Testing & Commissioning of anti-corrosive bobbin wound Fiber Glass Commercial Sand Filter having size of 2000 mm dia & flow rate 125 m ³ per hour at maximum working pressure is 2.5 kg/cm ² complete with collector arms and diffusers made from unplasticised PVC and polypropelene (Make :- Watermate /ASTRAL/Aquanomics/Aqvastar)		Nos.	
9	20000.00	Supply, installation & commissioning of graded filter media for commercial sand filter - Make: Watermate /ASTRAL/Aquanomics/Aqvastar		Kg	
10	4.00	Supply, Instalation, Testing & Commissioning of way-valve battery assembly suitable for 125 m3 filter of 2000mm dia complete with drain and air purging arrangement- Make :- Watermate /ASTRAL/Aquanomics/Aqvastar		Nos.	
11		Supply, Installation & Commissioning of Centrifugal Recirculation Pump with Hair/Leaf Strainer. Port Size: 100 x 100 Phase:Three Power: 10 HP Electric Motor working on 400/440 V, 50 Hz, 3 Phase Electric supply with coupling & base frame etc complete Make:Kirloskar/Texmo/Grundfos / Xylem		Nos.	
	5.00	125 m ³ / 8 mtr Head		Nos.	
12	4.00	Supply & Installation, Testing & Commissioning of Dosing Pumps capacity 35 mtr Head, 0-5 ltrs per Hour. Complete with 6 Amp Switch Socket arrangement as required FRP Tank for preparation of solution, Capacity 200 ltrs. with stirrer etc. complete. (Make :- Watermate/Oceanstar/ EDOSE/Nuton/Accord)		Nos.	
13	2.00	Supply & Installation, Testing & Commissioning of Pool main drain cover with stainless steel base plate of size 450mm x 450mm - Make: Watermate /ASTRAL/Aquanomics/Aqvastar		Nos.	
14	120.00	P & F of ABS pool inlet nozzel - Make: Watermate /ASTRAL/Aquanomics/Aqvastar		Nos	

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 11:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

15	110.00	ABS gratings in white color 12" wide Make:Watermate /ASTRAL/Aquanomics/Aqvastar		rm	
16	1.00	Supplying Electric Control Panel suitable to operate filtration system with GSM Based Real-Time Monitoring System having necessary sensors & Web-based application to indicate the following parameters- 1. Hours of Operation 2. Flow 3. Chlorine Level 4. Turbidity 5. pH Level Also including, flow meters, flow sensors, sampling valves, single board computers with USB & HDMI port, pen drive for data logging, modem for real time monitoring and Inos 32" LED Display screen. Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Job	
17	2.00	304 grade 4-steps stainless steel ladders with anti skid pads Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
18	4.00	304 grade 5-steps stainless steel ladders with anti skid pads Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
19	2.00	Stainless Steel Trolley mounted suction sweeper pump of 2.0 HP Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
20	2.00	Delux leaf net bag type Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
21	2.00	Delux wall brush with SS back Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
22	2.00	Stainless steel algae brush Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
23	2.00	24" Stainless steel vaccum head with wheels, brush, wiper and 125 m towing rope Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
24	2.00	Floating Hose pipe 15 M Make:Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
25		Standerd Telescopic handle 1.2m-2.4m, 2.4m-4.8m Make :Watermate /ASTRAL/Aquanomics/Aqvastar			
a	2.00	1.2m-2.4m		Each	
b	2.00	2.4m-4.8m		Each	
26	2.00	Basic pH and CI test kit Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
27	2.00	Hardness Test kit Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
28	200.00	TCCA-90 chlorine granules for disinfection Make :Watermate /ASTRAL/Aquanomics/Aqvastar		kg	
29	9.00	50m racing lane with anchors Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
30	20.00	Starter Blocks for jumping with adjustable non-slip platform along with all anchoring fixtures and numbering as per FINA specification. Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
31	2.00	P/F Back stroke indicator with stainless steel stanchions, PVC or fabric flags, ropes and pole anchors Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
32	2.00	P/F False start rope with stainless steel stanchions, false start ropes, fittings and pole anchors Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	

Signature valid

Digitally signed by Rajkesh Meena
Designation : Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

33	2.00	P/F Aluminium life saving hook with telescopic handle Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
34	2.00	P/F Lifebuoy made of UV grade PE & PU foam filled, round shaped with retro reflective tape and grab line Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
35	2.00	P/F Life Jacket made of durable, water resistant fabric that resist chlorine and UV degradation Make :Watermate /ASTRAL/Aquanomics/Aqvastar		Each	
36	4.00	Supply, Instalation, Testing & Commissioning of U.V. Sterlizer with S.S. Housing outside, U.V. Lamp, glass tube and all other accessories with supports, inlet outlet connection with bypass arrangement complete with required accessories. Watermate /ASTRAL/Alfaa UV Flow rate = 125000 Ltr/Hr working Pressure = 2.5 Kg/Sqm		Nos.	
D		Basketball Court			
1	1394.00	Synthetic PU Flooring 7+2mm Supplying and Installation of synthetic outdoor Sports Flooring system of 7mm thick composed of spormat high quality recycled rubber granules and polyurethane elastomers of thickness 7mm, tensile strength DIN 53571: 0.6-1 mPa coated with PU pore sealer and self leveling wear coat and top coat with 2 mm Polyurethane system , Approved by BWF & FIBA With specifications of (i) Force Reduction (EN 14808): > 25% ; (ii) Standard Deformation :>0.5mm ; (iii) Rolling load :1500N; (iv) Ball Bounce : 100 % .,v) Impact Resistance: 18Nm.Total thickness Minimum : 9mm		Sqm	
2		Supplying & Installation of Basket Ball Post including Acrylic basketball back board of thickness 25mm with steel frames fitted in the main frame and its support complete in all respect with nuts, bolts, base plate,concrete at base etc as per the specification of FIBA. Basketball 6" pipe System made of 6" pipe with 14swg 1" x 1" square CR pipe 16 SWG double cross support for extra strength. Finishing works like painting of One coat of red oxide and two coats of UV protected best white enamel. The basket ring is coated with orange colour best enamel paint.			
		Providing & fixing Basketball Ring and Ring net of approved brand and FIBA Standards			
	1.00	Rates of item to include all the above operations including material machinerries and labour etc. all complete and shall be installed in a manner that the equipment is ready to use and to the satisfaction of Engineer -In -Charge		Pair	
E		Volleyball Court			
1	193.80	Providing and laying crushed clay bricks in minimum thickness of 15cm it should be leveled well watered and compacted by roller.as directed by engineer in chagre.		Cum	
2	193.80	Providing and laying of approved class top surface of playfield with clay mix with sandy soil and wooden dust in approved ratio as per available characteristics of black cotton soil layed with Proper grinding, screening and compaction by using water		Cum	
3	212.00	Laying of brick lining in outer edge of court and whitening with approoved quality as directed by EIC.		Rmt	
4		Supplying and Installation of Volley Ball post with ISI standard "C" Class GI Pipes of 3" Inner dia with a height 2.43m for men and 2.24m for women above ground level, a			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		minimum depth of 60cm pipe with welded clamps to be fixed below ground level and Concreted with CC 1:2:4 mix. Each pole provided with 2 Nos. of 3" pulleys with 1 No of Ratchet and 1 No hook The item rate includes finishing works like painting with best quality white enamel paint over the priming Coat and shall be installed in a manner that the equipment is ready to use and complete in all respect to the entire satisfaction of Enginner In Charge			
		Standard approved quality net shall be of 1m wide and of 10m long with the mesh of 10 cm x10cm double thread thickness and 5cm wide canvas or Rexin stitched over the top and bottom and a flexible cable passes through the Canvas / Rexin at upper edge of the net. (Two nos. will be supplied and one no. will be Spare)			
	2.00	Flexible Antenna 1.80m height and 10mm in diameter made of fibre glass or similar materials place on the outer edge of the side band 80cm of each antenna extends above the net and marked with 10cm strips width having contrasting colours such as Red and White alternately.		Each	
F		Kho-Kho Ground			
1	103.95	Providing and laying crushed clay bricks in minimum thickness of 15cm it should be leveled well watered and compacted by roller.as directed by engineer in chagre.		Cum	
2	103.95	Providing and laying of approved class top surface of playfield with clay mix with sandy soil and wooden dust in approved ratio as per available characteristics of black cotton soil layed with Proper grinding, screening and compaction by using water		Cum	
3	108.00	Laying of brick lining in outer edge of court and whitening with approved quality as directed by EIC.		Rmt	
G		Kabaddi Ground-2			
1	94.50	Providing and laying crushed clay bricks in minimum thickness of 15cm it should be leveled well watered and compacted by roller.as directed by engineer in chagre.		Cum	
2	94.50	Providing and laying of approved class top surface of playfield with clay mix with sandy soil and wooden dust in approved ratio as per available characteristics of black cotton soil layed with Proper grinding, screening and compaction by using water		Cum	
3	180.00	Laying of brick lining in outer edge of court and whitening with approved quality as directed by EIC.		Rmt	
H		Handball Ground			
1	158.40	Providing and laying crushed clay bricks in minimum thickness of 15cm it should be leveled well watered and compacted by roller.as directed by engineer in chagre.		Cum	
2	158.40	Providing and laying of approved class top surface of playfield with clay mix with sandy soil and wooden dust in approved ratio as per available characteristics of black cotton soil layed with Proper grinding, screening and compaction by using water		Cum	
3	120.00	Laying of brick lining in outer edge of court and whitening with approved quality as directed by EIC.		Rmt	

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

4	1.00	Providing, supplying, installing, testing and commissioning (SITC) of International Handball Federation (IHF) approved Handball Goal Post of clear opening size 3000 mm × 2000 mm, fabricated from heavy-duty extruded aluminium alloy section of 80 mm × 80 mm with rounded edges, polyester powder-coated in alternate red and white bands as per IHF regulations, complete with aluminium rear net support frame, UV-stabilized polypropylene goal net, nylon/stainless steel net hooks, stainless steel (SS 304) hardware, floor sockets with locking arrangement/portable anti-tip anchoring system, all accessories, fixtures and fittings, including erection, alignment, testing and commissioning, complete in all respects, conforming to EN 749, IHF Goal Regulations and as directed by the Engineer-in-Charge.		Each	
---	------	---	--	------	--

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

Schedule "G"

S. No.	Quantity	Particular	Rate	Unit	Amount
		Walking Track			
1	3900.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m.	9.00	sqm	35100.00
2	630.00	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	178.00	Cum	112140.00
3	500.00	Supplying chemical emulsion in sealed containers including delivery as specified. Chlorpyrifos/Lindane emulsifiable concentrate of 20%	243.00	ltr	121500.00
4	3450.00	Diluting and injection Chlorpyrifos Emulsifiable concentrate 20% with 1% concentration for PRE-CONSTRUCTIONAL Anti termite treatment as per IS 6313 part III as amended from time to time and creating a continuous chemical barrier under and around the column pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall and floor along the external perimeter of building expansion joints, over the top surface of consolidated earth of which aproch is to be laid surrounding of pipes and conduits etc. complete as per specification (Plinth floor area only shall be measured for payment and excluding the cost of chemical emulsion) .	47.00	sqm	162150.00
5		Construction of Embankment with Material Obtained from Borrow Pits			
	1435.50	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300-1 and 300-2 with a lead upto 5000 m as per MoRTH Specification Clause 305.3	58.00	Cum	83259.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

7		Providing laying spreading and compacting specified graded sand, gravel (crushed stone) as per Table 400- 1,400-2 or any other course material as per design mix, as per CBR in sub base course including premixing the material at OMC in wet mix plant, carriage of mixed material spreading in uniform layers with motor grader F.E loader on a prepared base and compacting with vibratory roller to achieve desired density (as per I.S.2720) including all material, labor, machinery, lighting guarding, barricading and maintenance of diversion complete.[MoRTH specification : Clause 401]. By mechanical means.			
	552.00	For Grading-I Material	502.00	cum	277104.00
8	552.00	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400-12 & 400-13 and MoRTH Specification Clause 406.	882.00	cum	486864.00
9	2415.00	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base(WBM/WMM) including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per MoRTH Specification Clause 502	31.00	sqm	74865.00
10	2415.00	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per MoRTH Specification Clause 503.	11.00	sqm	26565.00
11		Providing and laying bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500-7 premixed with bituminous binder, transported to site with all leads laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per MoRTH Specification Clause 504.			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

	120.75	Bitumen (VG-30)	6613.00	cum	798519.75
12		Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder minimum @ 5.2 & 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH Specifications Clause 507 complete in all respects			
	72.45	for Grading-II(13 mm nominal size) Bitumen (VG-30)	7925.00	Cum	574166.25
13	120.00	Providing and laying of paver block as per IS 15658 : 2006 (Indian standard for precast concrete block for paving - specification) and IRC : SP:63-2004 (guidelines for the use of interlocking concrete block pavement) , M-40, 80mm thick to be used in medium - traffic (medium traffic is defined as a daily traffic of 150-450 commercial vehicle exceeding 30KN laden weight or an equivalent of 0.5 to 2.0 MSA for a design life of 20 years.) like city street, small and medium market roads, low volume roads, utility cuts on arterial roads, etc Category A Denated units to key into each other on four faces zigzag shapes as per IRC SP 63:2004	1521.00	Sqm	182520.00
14	155.25	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement : 3 coarse sand) including making joints with without grooves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete including painting etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineerin- charge).	6103.00	Cum	947490.75
15		P&F G.I Pipes (External work) with G.I fittings excluding union (IS: 1239 Mark) including trenching & refilling earth etc.			
a	1000.00	50mm dia nominal bore. B Class	491.00	Rm	491000.00
b	100.00	25mm dia nominal bore. B Class	278.00	Rm	27800.00
16		Supply & fixing G.I union ISI marked in G.I pipe line as required complete in all respect of size.			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

a	100.00	25mm dia nominal bore.	164.00	Each	16400.00
b	120.00	50mm dia nominal bore.	463.00	Each	55560.00
17		P&F Full-Totaly valve (IS:778 Mark) or wheel valve of approved make.			
a	20.00	(Gun Metal) 50mm nominal bore.	1464.00	Nos.	29280.00
b	100.00	(Gun Metal) 25mm nominal bore.	529.00	Nos.	52900.00
18		Supply of PVC hose pipe of different sizes at store including transportation etc. complete :			
	200.00	25mm dia.	80.00	R.Mtr.	16000.00
19	282.00	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, for all lift and lead, including getting out the excavated soil and disposal of surplus excavated soils as directed, within all lead and lift.	178.00	Cum	50196.00
20		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
	28.20	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	3302.00	Cum	93116.40
21		Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in:			
	264.38	Cement Mortar 1:6 (1-Cement : 6-Sand). Upto plinth	2838.00	Cum	750296.25
22	211.50	Providing & fixing precast cement concrete coping 1 : 2 : 4 mix 50mm thick complete as per specification :	367.00	Sqm	77620.50
23		Plaster on new surface on walls in cement sand mortar 1:4 including racking of joints etc. complete fine finish :			
	846.00	25mm thick	227.00	Sqm	192042.00
24	564.00	Finishing Toe wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding	53.00	Sqm	29892.00
		New work (Two or more coats applied @ 3.84 kg/10 sqm).			
25		Supplying and fixing of chain link fencing with angle iron posts 50x50x6mm placed at every 3 Mtr. apart 30cm in ground embedded in cement concrete 1:3:6 (30x30x45cm) corner and every tenth post to be strutted with (50 x 50 x 6cm)			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		angle iron provided and fixed and fitted with posts including earth work in excavation etc. complete with chain link size.			
	846.00	50mm x 50mm x 3.15mm	629.00	Sqm	532134.00
26		Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :			
	2199.60	Two or more coats on new work	69.00	Sqm	151772.40
		Covering of Sitting Tiers			
1	230.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50 Mtr. and lift up to 1.5 Mtr. : All kinds of soil	9.00	Sqm	2070.00
2	572.88	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	178.00	Cum	101972.64
3	270.86	Filling available excavated earth (excluding rock) in trenches, plinth side of foundation etc. in layers not exceeding 20 cm. in depth, consolidating each deposited layer by ramming and watering including lead up to 50 meter and with all lift.	64.00	Cum	17335.30
4		Supply & Stacking good soil of earth at site complete including loading unloading & Transportation etc.			
	99.00	Good soil of earth	13.50	Cum	1336.50
5	347.20	Diluting and injection Chlorpyrifos Emulsifiable concentrate 20% with 1% concentration for PRE-CONSTRUCTIONAL Anti termite treatment as per IS 6313 part III as amended from time to time and creating a continuous chemical barrier under and around the column pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall and floor along the external perimeter of building expansion joints, over the top surface of consolidated earth of which aproch is to be laid surrounding of pipes and conduits etc. complete as per specification (Plinth floor area only shall be measured for payment and excluding the cost of chemical emulsion)	47.00	sqm	16318.40
6	100.00	Supplying chemical emulsion in sealed containers including delivery as specified. Chlorpyriphos/Lindane emulsifiable concentrate of 20%	243.00	ltr	24300.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

7		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
a	101.58	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	3302.00	Cum	335417.16
	9.00		334.00	Sqm.	3006.00
8	207.18	Centering and Shuttering with plywood or steel sheets including strutting, propping bracing both ways and removal of formwork for foundation , footings, strap beam, raft , bases of columns etc.		Sqm	
9		Centering & shuttering with plywood or steel sheets including strutting, propping bracing both ways with steel props and removal of formwork for upto floor five level for :			
c	225.00	Columns, pillars, posts and struts etc.	157.00	Sqm.	35325.00
10		Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor five level. ('Original producers' who manufacture billet directly from iron ores and roll the biletts to produce steel conforming to IS:1786)			
a	45366.30	Thermo-mechanically Treated bars (Conforming of relevent IS code)	77.00	Kg	3493205.10
11	275.45	Providing and laying in position specified grade of cement concrete for all RCC structural elements upto plinth level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plastizers(if required) excluding the cost of centering, shuttering and reinforcement. M20 grade Nominal Mix / Design Mix	4934.00	Sqm.	1359045.63
12	48.60	Providing and laying in position specified grade of cement concrete for RCC structural elements upto floor five level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plastizers (if required) excluding the cost of centering, shuttering and reinforcement for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. M20 grade Nominal Mix / Design Mix	5609.00	Cum	272597.40
13		Add extra for providing richer mixes respectively at all floor levels			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

a	324.05	Providing M-25 grade concrete by using min 410 kg of cement per cum instead of M-20 grade design mix.	69.00	Cum	22359.11
14		Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in:			
	10.80	Cement Mortar 1:6 (1-Cement : 6-Sand). Upto plinth	2838.00	Cum	30650.40
15	50.00	Plaster on new surface on walls in cement sand mortar 1:6 including racking of joints etc. complete fine finish : 20 mm thick	911.00	Sqm.	45550.00
16	50.00	Providing and applying white cement based putty over plastered surface to prepare the surface even and smooth complete (New plastered surface three or more coats)	84.00	Sqm	4200.00
17		Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade including all scaffolding:			
a	50.00	Two or more coats on new work including preparation of base with primer, putty, lippy etc complete in all respect.	80.00	Sqm	4000.00
18		Providing and laying of paver block as per IS 15658 : 2006 (Indian standard for precast concrete block for pavingspecification) and IRC : SP:63-2004 (guidelines for the use of interlocking concrete block pavement)			
		M-30, 60 mm thick to be used in non traffic areas like buildingpremises, monument premises, land scapes, public gardens/park, domestic drives, paths and patios, Embankment slopes,sand stabilization Area etc.(As per table 1 of IS 15658:2006			
	220.00	Category A Denated units to key into each other on four faces zigzag shape as per IRC SP 63:2004	816.00	Sqm	179520.00
19	8.78	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement : 3 coarse sand) including making joints with without grooves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete including painting etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineerin- charge).	6103.00	Cum	53553.83

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		Swimming Pool			
1	3630.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	5.00	sqm	18150.00
2	3630.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50 Mtr. and lift up to 1.5 Mtr.: All kinds of soil	9.00	Sqm	32670.00
3	1767.02	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	178.00	Cum	314530.27
4	55.00	Add extra for foundation/trenches/drains for every additional lift of 1.5 Mtr. or part thereof in 1.26.1 All kinds of soil	34.00	Cum	1870.00
5	500.00	Supplying chemical emulsion in sealed containers including delivery as specified. Chlorpyrifos/Lindane emulsifiable concentrate of 20%	243.00	ltr	121500.00
6	3300.00	Diluting and injection Chlorpyrifos Emulsifiable concentrate 20% with 1% concentration for PRE-CONSTRUCTIONAL Anti termite treatment as per IS 6313 part III as amended from time to time and creating a continuous chemical barrier under and around the column pits, wall trenches, basement excavation, top surface of plinth filling, junction of wall and floor along the external perimeter of building expansion joints, over the top surface of consolidated earth of which aproch is to be laid surrounding of pipes and conduits etc. complete as per specification (Plinth floor area only shall be measured for payment and excluding the cost of chemical emulsion)	47.00	Sqm	155100.00
7	282.48	Filling available excavated earth (excluding rock) in trenches, plinth side of foundation etc. in layers not exceeding 20 cm. in depth, consolidating each deposited layer by ramming and watering including lead up to 50 meter and with all lift	64.00	Cum	18078.72
8	207.98	Supply & Stacking good soil of earth at site complete including loading unloading & Transportation etc. Good soil of earth	44.00	Cum	4004.44

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

9	1735.70	Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level M10 grade Nominal Mix 1: 3: 6 (1 cement : 3 coarse sand : 6 graded	3302.00	Cum	5731294.61
		1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).			
10	194.73	Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level M10 grade Nominal Mix 1: 3: 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size).	3847.00	Cum	749126.31
11	670.69	Providing and laying in position specified grade of cement concrete for all RCC structural elements upto plinth level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plastizers(if required) excluding the cost of centering, shuttering and reinforcement. M20 grade Nominal Mix / Design Mix	4934.00	Cum	3309183.48
12	148.33	Providing and laying in position specified grade of cement concrete for RCC structural elements upto floor five level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plastizers (if required) excluding the cost of centering, shuttering and reinforcement for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. M20 grade Nominal Mix / Design Mix	5609.00	Cum	831977.22
13	915.41	Providing and laying in position specified grade of cement concrete for RCC structural elements upto floor five level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plastizers(if required) excluding the cost of centering, shuttering and reinforcement for Beams, suspended floors, roofs, griders having slopes up to 15°, landings, balconies, shelves, chajjas, lintels, bands, plain windows sills, staircases and spiral staircases etc.M20 grade Nominal Mix / Design Mix	5185.00	Sqm	4746394.50
i	915.41	Providing M-30 grade concrete by using cement as per codal provision instead of M-20 grade design mix.			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

14	90.02	Centering and Shuttering with plywood or steel plate including strutting, propping bracing both ways and removal of formwork for foundation , footings, strap beam, raft , bases of columns etc.	157.00	Sqm	14133.39
15		Centering & shuttering with plywood or steel sheets including strutting, propping bracing both ways with steel props and removal of formwork for upto floor five level for :			
i	1332.38	Walls (any thickness) including attached pilasters, buttresses plinth and string course.	289.00	Sqm	385058.86
ii	692.05	Suspended floors, roofs, landings, staircases, balconies, girders, cantilevers, bands, coping bed plates, anchor blocks, sills, chhajjas, lintel, beam, plinth beam etc.	340.00	sqm	235297.00
iiii	100.80	Columns, pillars, posts and struts etc.	375.00	sqm	37800.00
16	114426.10	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor five level. ('Original producers' who manufacture billet directly from iron ores and roll the billets to produce steel conforming to IS:1786)	77.00	Kg	8810809.70
		Thermo-mechanically Treated bars (Conforming of relevent IS code)			
17	207.39	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement mortar 1 : 6 (1 cement : 6 coarse sand)	4990.00	Cum	1034899.05
18	17.01	Add extra for Square or Rectangular Pillars in Superstructre brick work up to five storey Upto 45 cm length and all sides are free	327.00	Cum	5562.27
19	76.40	Half brick masonry in Superstructure , above plinth level upto floor Three level using bricks of designation 75 Cement mortar 1 : 4 (1 cement : 4 coarse sand)	497.00	sqm	37970.80
20	288.40	Random rubble dry stone Kharanja under floor.	932.00	Cum	268788.80
21	437.87	Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in: Cement Mortar 1:6 (1-Cement : 6-Sand).	2838.00	Cum	1242677.90
22	259.25	Providing and fixing Granite stone slab mirror polished and machine edge cut in walls, pillars, steps, Shelves, Sills Counters, Floors etc. laid on 12mm (Av.) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) jointing with white cement mortar 1:2 (1white cement : 2 marble dust) with pigment to match the shade of the marble slab including grinding, rubbing and polishing complete.Jhunjhunu / Jalore	3028.00	Sqm	785009.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		(Red/Chocolate/Black/Pink Colour)Above 3601 Cm2 Slabs			
23		Extra for providing edge moulding to 15-18mm thick marble/ Granite stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.			
		Granite/Kota Stone Work			
	30.00	Full Edge moulding	233.00	mtr	6990.00
	5.00	Half Edge moulding	143.00	mtr	715.00
24	112.13	Providing and fixing 1st quality MAT finished ceramic tile size 300x300mm confirming to IS : 13755 and IS : 15622 colour such as white, grey, ivory, fume red brown, light green, light blue and other light shades in floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (including the cost of cement mortar bed	748.00	Sqm	83870.10
25	11.21	Extra for using Marble printed / Granite shade or dark shade tiles instead of white, grey, ivory, fume red brown, light green, light blue and other light shades in glazed tiles and MAT finished tiles.	748.00	Sqm	8387.01
26	119.62	Providing and fixing 1st quality MAT & GLOSSY finished ceramic tile confirming to IS : 13755 and IS : 15622 colour such as white, grey, ivory, fume red brown, light green, light blue and other light shades in floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (including the cost of cement mortar bed 1:4). Size 300mm x 600mm	894.00	Sqm	106936.70
27	57.38	Supplying and fixing rolling shutters of approved make, made of 80 x 1.25mm. M.S. laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete including cost of spring hooks, providing and fixing necessary 25.3cm. long wire springs grade No. 2 and M.S. top cover 1.25mm thick for rolling shutters as per design & IS 6248-1979. (Clear openable area to be measured for payment).	2074.00	Sqm	118995.75

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

28	24.50	Providing and fixing in position collapsible steel shutters with vertical M.S. Channels 20 x 10 x 2mm and bracket with flat iron diagonals 20 x 5mm. size with top and bottom rail of Tiron 40 x 40 x 6mm. with 40mm dia steel pulleys/ball bearing complete with bolts, nuts locking arrangements inside and outside stoppers, handles etc. as per specification including applying a priming coat of approved steel primer. (To be measured and paid as per outer dimension).	5174.00	Sqm	126763.00
29	124.80	Providing and fixing aluminum work for doors ,windows, ventilators and partition with extruded built up standard tubular / appropriate Z sections and other sections of approved make conforming to IS :733 and IS :1285, fixed with rawl plugs and screws or with fixing clips ,or with expansion hold fasteners including necessary filling up of gap. at junctions , at top ,bottom and sides with required PVC/neoprene felt etc. Aluminium section shall be smooth ,rust free, straight ,mitered and jointed mechanically wherever required including cleat angle Aluminium snap beading for glazing /paneling , C.P. brass/ stainless steel screws Al. Tower bolt & Al. handle & Al. Aldrop etc.,all complete as per architectural drawings and the directions of Engineer- in – charge .(Glazing and paneling to be paid for separately). For fixed portion Powder coating aluminum (minimum thickness of powder coating 50 micron)	351.00	sqm	43804.80
30	41.85	For shutters builtup standard tubular sections of openable doors ,windows & ventilators including providing & fixing hinges / rollers etc. and making provision for fixing of fittings wherever required (lockes shall be paid for separately). Powder coating aluminum (minimum thickness of powder coating 50 micron)	381.00	sqm	15944.85
31	41.85	Providing and fixing glazing in aluminium door, window ,ventilator shutters and partitions etc. with PVS / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge.(Cost of aluminium snap beading shall be paid in basic item.) With float glass panes of 5.0 mm thickness (weight not less than 13.50 kg/sqm)	902.00	Sqm	37748.70

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

32	1.00	Providing and fixing double action hydraulic floor spring of approved brand and manufacture IS : 6315 marked, for doors including cost of cutting floors as required, embedding in floors and cover plates with brass pivot and single piece M.S. With stainless steel cover plate	1426.00	nos	1426.00
33	1.00	Providing and fixing 100mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	328.00	Each	328.00
34	2.00	Providing and fixing aluminium round shape handle of outer dia 100mm with SS screws etc. Complete as per direction of Engineer-in-charge Powder coated minimum thickness 50 micron aluminium	73.00	Each	146.00
35	15.60	Providing and fixing expanded grill made of aluminum as per design and drawing having members section of size 7.5mm x 6.0mm and opening of size 102mm x 99mm to aluminum window/vent with required screws, Y and H aluminium sec (as per drawing) at the ends and middle joints respectively complete in all respect as per direction of engineer in charge. Powder coating aluminum (minimum thickness of powder coating 50 micron)	1843.00	sqm	28750.80
36	21.60	Filling the gap upto 5 mm depth and 5 mm width in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.	78.00	Mtr	1684.80
37	250.00	Providing and fixing stainless steel railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). Grade 304	503.00	kg	125750.00
38	1200.00	Providing and fixing steel gate, grating , and grills made of angles, tees, square bars, flats,or black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat of red oxide	96.00	kg	115200.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

39	450.00	Extra if square,rectangular hollow tubelar sections are used or grill made by flats only	9.60	kg	4320.00
40	1940.00	Plaster on new surface on walls in cement sand mortar 1:4 including racking of joint etc. complete fine finish : 20mm thick	202.00	Sqm	391880.00
41		Plaster on new surface on walls in cement sand mortar 1:6 including racking of joints etc. complete fine finish :			
a	1144.00	20 mm thick	190.00	Sqm	217360.00
b	276.50	12mm thick. Ceiling	163.00	Sqm	45069.50
c	501.28	20mm thick.(Internal plastr)	202.00	Sqm	101258.56
42	933.34	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade including all scaffolding: Two or more coats on new work including prepartion of base with primer, putty, lippy etc complete in all respect. Two or more coats on new work including prepartion of base with primer, putty, lippy etc complete in all respect.	80.00	Sqm	74666.88
43	2077.34	Providing and applying white cement based putty over plastered surface to prepare the surface even and smooth complete New Plastered Surface (three or more coats) New Plastered Surface (three or more coats)	84.00	Sqm	174496.22
44	25.40	Grading roof for water proofing treatment with water proffing compound)Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	4483.00	Cum	113868.20
45	500.00	Making grooves as per design in plaster 10mm to 20mm wide.	7.00	Rm	3500.00
46	300.00	Making of drip course (Tapka) in cement sand mortar 1:6 width upto 40 mm and 10 mm thick as per approved design	11.00	Rm	3300.00
47	500.00	Extra for making Ornamental design like Kangooras Gola etc. as per Jaipur practice in cement plaster	95.00	Rm	47500.00
48	160.00	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10mm and down gauge) including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design	111.00	Rmt	17760.00
49	10.00	Making khurras 450 x 450mm with average minimum thickness 50mm cement concrete 1 : 2:4 over P.V.C. Sheet 1 Mtr. x 1 Mtr. x 40micron finished with 12mm cement plaster 1 : 3 and one coat of neat cement, rounding edges and making and finishing the out let complete.	154.00	Each	1540.00
50	37.50	Providing & fixing 12 mm thick tegular edge Glass Fibre Reinforced Gypsum False ceiling tiles	1365.00	sqm	5177.50

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		of size 595 x 595 mm in true horizontal level suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanized @ 170 gsm/sqm.) consisting of main “T” runner with suitably spaced joints to get required length and of size 24x38mm made from 0.30mm thick (minimum) sheet spaced at 1200mm center to center and cross “T” of size 24x25mm made of 0.30mm thick (minimum) sheet, 1200mm long spaced between main “T” at 600mm center to center to form a grid of 1200x600 mm and secondary cross “T” of length 600mm and size 24x25mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600mm panel to form grids of 600x600mm and wall angle of size 21x21x0.30 mm and laying false ceiling tiles of approved texture in the grid including, wherever, required, cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main “T” runners to be suspended from ceiling using GI slotted cleats fixed to ceiling with 6 mm dia and 50mm long dash fasteners, 4mm GI adjustable rods with galvanised level clips spaced at 1200mm center to center along main T, bottom exposed width of 24mm of all T-sections shall be pre-painted with polyester paint, all complete at all heights as per specifications drawings and as directed by Engineer-in-Charge.			
51	18.17	Providing and fixing external grade board solid core single leaf flush door shutters ISI 2202-67 marked using Phenol formal dehyderesin in glue both sides with approved steel fittings complete as per annexure 'A' : 35 mm thick . Commercial veneer both side	2248.00	sqm	40834.92
52	18.17	Providing & Fixing mica of approved make for inner/outer side of shutters with fevicol & nails complete as per approved by engineer in charge.0.8mm thick mica	762.00	Sqm	13841.73
53	18.17	Extra for providing external lipping with 2nd class teak wood battens 6 mm minimum depth on all edges of shutters (over all area of door shutter to be measured) Over item no. 8.13.	141.00	sqm	2561.27
54	42.25	Providing and fixing pressed steel door frames confirming to IS 4351 manufactured from commercial mild steel sheet of 1.25 mm thickness including hinges jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25mm, or base ties of 1.25mm pressed mild steel welded or rigidly fixed together by mechanical means, adjustable lugs with split end	429.00	Rmt	18125.25

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		tail to each jamb including steel butt hinges 2.5mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface including filling with CC 1:2:4(M15 grade) complete as directed by Engineer-in-charge : Profile B			
55	20.92	Providing and fixing factory made P.V.C. door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2 Nos. of 150mm long brackets of 15x15mm M.S. square tube, the vertical door profiles to be reinforced with 19x19mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100mm size complete as per manufacturers specification and direction of Engineer-in-Charge.	277.00	sqm	5793.73
56	60.36	Providing and fixing to existing door frames.	3347.00	Sqm	202024.92
		30mm thick factory made solid both side Pre laminated panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for stiles and 15x15mm top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture M.S. frame covered with 5mm thick heat moulded PVC 'C channel of size 30mm thickness, 70mm width out of which 50mm shall be flat and 20mm shall be tapered in 45 degree angle on either side forming stiles; and 5mm thick, 95mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75 mm shall be flat and 20mm shall be tapered on both sides to form lock rail. Top bottom and lock rails shall be provided either side of the panel. 10mm (5mm x 2) thick, 20mm wide cross PVC sheet shall be provided as gap insert for top rail & bottom rail. Panelling of 5mm thick PVC sheet to be fitted in the M.S. frame welded/ sealed to the stiles & rails with 7mm (5mm +2mm) thick x 15mm wide PVC sheet bending on inner side, and joined together with solvent cement adhesive. An additional 5mm thick PVC strip of 20mm width is to be stuck on the interior side of the 'C Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacture's specification & drawing.(For W.C.and bathroom door shutter).			
57	1144.00	Finishing walls with textured exterior paint of	404.00	sqm	4176.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		required shade as per approved colour complete as per manufacturers specifications including primer coat and protecting coat including scaffolding and safety provision Trowel Finish av. thickness 1500 to 2000 microns.			
58	300.00	Providing and laying of paver block as per IS 15658 : 2006 (Indian standard for precast concrete block for paving specification) and IRC : SP:63-2004 (guidelines for the use of interlocking concrete block pavement) M-30, 60 mm thick to be used in non traffic areas like building premises, monument premises, land scapes, public gardens/park, domestic drives, paths and patios, Embankment slopes, sand stabilization Area etc.(As per table 1 of IS 15658:2006 Category A Denated units to key into each other on four faces zigzag shape as per IRC SP 63:2004	816.00	sqm	244800.00
59	20.25	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement : 3 coarse sand) including making joints with without grooves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete including painting etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineerin- charge).	6103.00	Cum	123585.75
60	254.00	Providing and fixing 20 mm thick precast terrazo tiles of approved make, with marble chips of size upto 6mm laid over roof with neat cement slurry mixed with pigment to match the shade of the tiles, including cutting ,grinding rubbing with machine complete on 20 mm thick bed of cement sand mortar 1 : 4. Light shade using white cement.	542.00	sqm	137668.00
61		Providing & laying Chequered terrazzo tiles of approved make 22mm thick with marble chips of size upto 6mm, in floors, jointed with neat cement slurry mixed wit pigment to match the shade of tiles including rubbing and polishing complete in all respect as per specification, on 28mm thick bed of C.M. 1:4 :			
	21.60	Light shade using shade cement.	684.00	Sqm	14774.40
62	4.00	P & F European type white glazed vitreous china 1st quality W.C pan (IS : 2556 Mark) with P or S trap including cutting and making good the wall and floor	2420.00	Each	9680.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

63		P & F water closet Seat Covers with brass hinges complete :			
	4.00	-do- White.	485.00	Each	1940.00
64	4.00	P & F C.P. lugs for toilet seat cover.	79.00	Pair	316.00
65		P & F 1st quality WVC Urinal (IS:2556 mark) with 25mm dia G.I. waste pipe, dome waste couplings, concealed iron brackets or screws etc complete.			
	6.00	Flat Back (large) or half stall size 610x400x80mm.	4637.00	Each	27822.00
66		P&F Marble Urinal Partition slab both sides polished of approved design cut from marble size 900x600mm.			
	4.00	Makrana 'Adanga' or Raj Nagar 1st Quality White or Andhi Indo-Italian marble.	801.00	Each	3204.00
67		P & F Low level Flushing Cistern of 10 litres capacity (IS : 2556mark). Of approved make with complete fittings C.I. brackets duly painted, brass ball cock with ball, (IS: 1703 mark) complete including cutting and making good the wall:			
	4.00	PVC with PVC bend and superior internal fittings	1645.00	Each	6580.00
68		P & F C.P. brass Urinal Flush Pipe set complete with flanged brackets of approved make.			
	6.00	For 1 Urinal	504.00	Each	3024.00
69	6.00	P & F C.P. brass Urinal Spreader for stall urinal of approved make.	363.00	Each	2178.00
70		P & F WVC Wash basin (1st quality IS:2556 Mark) of approved make with C.I. brackets duly painted 1 No. 15 mm C.P. Pillar cock (IS:8934 Mark) & 32 mm C.P. brass waste coupling of approved make, P.V.C Waste pipe with PVC nut 32 mm complete including cutting & making good the wall :			
	6.00	Size 630 mm x 500 mm dia for counter top	3265.00	Each	19590.00
71		P & F Bevelled edge Mirror/mirror with teak wood lipping around of special glass of approved make as per direction of Engineer-in-charge complete with 6mm thick commercial ply base fixed to wooden screws & washers.			
	5.00	Other sizes	1538.00	Sqm	7690.00
72		P & F Grating of approved quality/make:			
	20.00	Synthetic Material (PTMT) of approved quality/make size Square 150 x 150 x 8mm. (Anti Cockroach)	358.00	Each	7160.00
73		P & F Extension Pipe for bib cocks of approved quality/make.			
	10.00	C.P. brass of Heavy & Superior quality 100 X	119.00	Each	1190.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		15mm.			
74	4.00	P & F Jet spray for water closet with C.P. Copper Tube flange of approved make.	381.00	Each	1524.00
	10.00	Providing & fixing C.P.flange for 15mm dia taps.	18.00	Each	180.00
75		P & F Bath Shower of approved quality/make.			
	8.00	C.P. brass of Heavy & superior quality, revolving with adjustable key 150mm.	573.00	Each	4584.00
76		P & F Shower arm 15mm dia of approved quality/make.			
	8.00	C.P.brass heavy & superior quality 370 mm Projection.	376.00	Each	3008.00
77		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes (IS 15778 : 2007 code) having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1 metre spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. (Internal work Exposed on wall)			
	20.00	25 mm nominal size	282.00	mtr	5640.00
	50.00	32 mm nominal size	369.00	mtr	18450.00
78		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes (IS 15778 : 2007 code) having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. (Concealed work including cutting chases and making good the walls etc.,)			
	20.00	15 mm nominal size	279.00	mtr	5580.00
	40.00	20 mm nominal size	289.00	mtr	11560.00
	20.00	25 mm nominal size	376.00	mtr	7520.00
79		Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes (IS 15778 : 2007 code) having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings, this included jointing of pipes & fittings with one step CPVC solvent cement , trenching refilling & testing of joints complete as per direction of Engineer in Charge. (External work).			
	100.00	32 mm nominal size	343.00	mtr	34300.00
80		P & F Ball Cock (IS :1703 Mark) with Rod & P.V.C. Ball complete :			

Signature valid

Digitally signed by Rajkesh Meena
Designation : Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

	2.00	Brass wt. Not less than 600 gm, 25mm.	440.00	Each	880.00
81		P & F Full-way Valve (IS:778 Mark) or wheel valve of approved make :			
	2.00	Gun-metal 25mm nominal bore.	529.00	Each	1058.00
82		P & F Gun-metal Non-return Valve or Check Valve (IS : Make) of approved make, superior quality: 32mm nominal bore.			
	2.00	Vertical	583.00	Each	1166.00
83		P & F PVC Storage Tank ISI Marked (IS : 12701) indicating the BIS license No), of approved make with cover, 25mm dia 1M long G.I. overflow pipe & 25 Cm. long wash out pipe with plug & socket, including making connection etc., complete of approved design:			
	2.00	2000 LTR	15682.00	Each	31364.00
84		Hoisting Charges for each floor :			
	2.00	For items 2.26.5 to 2.26.8 (2 TANK X 2 FLOOR)	157.00	Each	314.00
85		Providing and fixing Superior quality CP Brass fittings of approved make as per direction of Engineer-in-charge			
	2.00	Long body Bib Cock 15 mm nominal size	1084.00	Each	2168.00
	24.00	Angular stop cock with long thread 15 mm nominal size	762.00	Each	18288.00
	4.00	Concealed stop cock 15 mm nominal size	1162.00	Each	4648.00
	8.00	Double coat hook	823.00	Each	6584.00
86	8.00	Wall mixer 3 in 1 system with provision of tefephonic bath shower with bend pipe	3743.00	Each	29944.00
87		P & F 15 mm. Dia Connection Pipe of approved quality/make : CP Brass Pipe with CP Brass nuts upto length 300mm.			
	24.00	(-do-) 600mm.	176.00	Each	4224.00
88	1.00	Fixing water meter (IS: 779 mark) and stop cock in G.I. pipe line including making chamber of approved size excluding cost of water meter & stop cock	308.00	Each	308.00
89		P & F water meter (IS : 779 mark) of approved make			
	1.00	25 mm dia	2378.00	Each	2378.00
90		Providing and Fixing Unplasticized Poly Vinyl Chloride (UPVC) SWR Pipes Type B for sciland waste discharge system (IS:13592 : 1992 Marked) of approved quality /make			
	20.00	75 mm dia	167.00	Mtr.	3340.00
	60.00	110 mm dia	336.00	Mtr.	20160.00
91		P&F rigid PVC pipe fittings (IS: 4985 mark) of approved quality /make including joining the pipe with solvent cement rubber ring and lubricant:			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

a		Coupler (socket)			
i	20.00	75 mm dia	72.00	Each	1440.00
ii	15.00	110 mm dia	108.00	Each	1620.00
b		Single Push Fit Coupler			
i	20.00	75mm dia	73.00	Each	1460.00
ii	15.00	110mm dia	127.00	Each	1905.00
c		Bend 45			
i	10.00	75mm dia	78.00	Each	780.00
ii	10.00	110mm dia	132.00	Each	1320.00
d		Bend 87.5			
i	10.00	75mm dia	94.00	Each	940.00
ii	10.00	110mm dia	155.00	Each	1550.00
e		Single Y			
i	8.00	75mm dia	144.00	Each	1152.00
ii	10.00	110mm dia	278.00	Each	2780.00
f		Single 'Y' with Door			
i	5.00	75mm dia	187.00	Each	935.00
ii	5.00	110mm dia	348.00	Each	1740.00
g		Pipe Clip			
i	50.00	110mm dia	31.00	Each	1550.00
h		Single Tee			
i	10.00	75mm dia	120.00	Each	1200.00
ii	10.00	110mm dia	210.00	Each	2100.00
I		Offset			
i	10.00	110mm dia	282.00	Each	2820.00
j		Vent Cowel			
i	10.00	110mm dia	59.00	Each	590.00
k	4.00	W.C. connector with ring	226.00	Each	904.00
i		110mm Dia			
l		Nahni trap			
i	15.00	110mm dia	171.00	Each	2565.00
m		Multi floor trap			
i	5.00	110mm dia	241.00	Each	1205.00
n		P- Trap			
i	4.00	110mm dia	382.00	Each	1528.00
o		Gully trap			
i	4.00	110mm dia	685.00	Each	2740.00
92		Providing & Laying C.C. 1:3:6 (Stone Agreegate 20mm nominal size) all around PVC Pipe including 7.5 cm thick bed concerte [Width & Height = Dia of Pipe in CM+15CM] excluding cost of Pipe & Excavation of trenches etc.			
	30.00	PVC pipe 110 mm dia	325.00	Mtr.	9750.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approver

RajKaj Ref No.:
24126045

M e-Sign

93		Raising manhole cover and frames slab to required level including dismantling existing slab and making good the damage as required (raising depth of manhole masonry to be paid separately).			
	5.00	Rectangular manhole 90x60 cm	5611.00	Each	28055.00
94		Construction of manhole in all type of soil inner size 90 X 60 Cm. 300 mm thick masonry in CM 1:6, 10 Cm. thick cement concrete 1:5:10 in foundation, 20 mm thick inside plaster in CM 1:6, finished with floating neat cement, 50mm thick M-15 grade C.C. flooring, making channels, 80mm thick stone slab covering with 40mm thick M-15 grade C.C. flooring, Cement cover with frame of 450mm dia, earthwork etc. complete as per design including disposal of surplus earth within 50 mtr. lead.			
	4.00	Depth up to 0.5 M	5489.00	Each	21956.00
	2.00	Add extra over item 3.19.1 for every additional 0.10m depth above 0.5 m depth.	206.00	Each	412.00
95		P & F Square-mouth gully trap 'A' grade (IS 651-1992 :marked) of approved make complete with C.I. grating, frame & Cover masonry chamber in C.M. 1:6, 100mm thick C.C. 1:5:10 base concrete, 40mm thick C.C.M-15 grade coping, 12mm thick cement plaster in CM 1:3 complete as per approved design & type.			
	4.00	Trap size 150 X 100mm, ferrow cement cover with frame, Internal Chamber size 300 X 300mm.	1150.00	Each	4600.00
96		Construction of chamber in all type of soil with 300 mm thick masonry in CM 1:6 m 10 cm thick C.C. 1:5:10 in foundation, 20mm thick insider plaster in Cm 1:6, finished with floating neat cement, 50mm thick M-24 grade C.C. flooring , earthwork etc. complete as per design including disposal of surplus earth within a lead of 50 mtr.			
	10.00	do- size 450 x 450mm depth upto 0.5 M Cement coverwith frame	2332.00	Each	23320.00
	5.00	-do- size 600 x 450mm depth upto 0.5 M Cement cover with frame.	3299.00	Each	16495.00
97	2.00	Construction of soakage well in all type of soil with 300 mm thick dry masonry, top and bottom 300 mm course in CM 1:6, 80mm thick stone slab, jointing of slab in CM 1 : 3, Ralthal, Kharanja, 40 mm thick M-15 grade C.C flooring , earthwork complete as per approved drawing including disposal of earth within a lead of 50 mtr.:	24135.00	Each	48270.00
		Size 300 CM Dia outside & 300 CM Depth			
98		Construction of septic Tank in all types of soil with 40 Cm .thick masonry in CM 1:6, 24 Cm thick C.C bed of 1:5:10, M-24 grade C.C flooring			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		& over stone slab covering ,80 mm thick slab ,jointing of slab in CM 1:3. Ralthal, Kharanja, 50 mm thick stone partition walls, 20 mm thick plaster in CM 1:6 finished with neat loading cement, 4 Nos C.I foot rests of approved design ,two No. 450 mm dia each Ferro cement cover with frame, earth work etc. complete as per approved drawing including disposal of surplus earth within a lead of 50 mtr:-			
	1.00	Size 400 x140x150 cm.(for 50 users) with 115 mm thick RCC (M-20) slab with Tor steel reinforcement 10mm ϕ @15 cm c/c bothways including shuttering complete in all respect.	59860.00	Each	59860.00
99	10.00	P & F M.S. Foot Rests in with C.M.,1:3, standard design in 20mm square M.S. bar 50 mm embedded in wall & 10 cms. projected out complete.	223.00	Each	2230.00
100	50.00	Supplying and fixing C.I. Cover with frame, C.I. gratings for chambers & man holes.	72.00	KG	3600.00
101		Supplying and fixing Ferro- cement cover with C.I. frame for chambers & man holes of size.			
	10.00	Rectangular shape 600 x 450 mm, to withstand 3 MT center point load & minimum unfractured load of 1 MT. (Light duty).	1357.00	Each	13570.00
102		SITC of Monoblock motor pump set ISI marked (IS:9079-2002) with TEFC motor, motor should be IE2 class as per IEC 60034-2-1: 2007, IEC 60034-30: 2008, & IS12615:2011. with Stainless steel Impellor, Stainless steel shaft, Mechanical seal, Single/Three phase (240 - 440 V) permanent split capacitor type (PSC), fitted with thermal overload protection, Including cost of hardware etc on existing platform complete. Pump shall have following HP Rating, phase, Head, minimum Discharge respectively complete in all respect. OEM shall have submit NABL / CPRI / ERDA accredited lab type test certificate before execution. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			
	2.00	3.0 HP, 3- ϕ , (14 - 26)Mtr, (760-600) LPM	35287.00	Each	70574.00
		(1 WORKING+1 STANDBY)			
103		SITC of Contactor OEM Fabricated DOL/Star-Delta Starter panel with switchgear selection as per Type-2 Coordination Chart and made out from 1.6 mm thick powder coated CRCA sheet, enclosure comprising of over load protection relay, short circuit & single phasing protection, Illuminated ON / OFF push buttons, ammeter, voltmeter, indicating lamps etc. suitable for			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		following rating motors complete in all respect. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			
	2.00	3.0 HP to 5.0 HP (DOL starter)	10173.00	Each	20346.00
104		Supply , Installation, Testing and Comissioning of IS:1475 marked self contained drinking water cooler with hermetically sealed compressor,non CFC refrigerent suitable for operation on 230V/1pH/50Hz AC supply,Full stainless steel (SS304)body (0.8 mm thick) and tank (0.5 mm thick) , stainless steel water tray,minimum two nos Brass Chrome plated faucets and suitable drainage system complete in all respect with required height MS fabricated and Painted Angle iron frame (Cost of frame to be paid Extra)complete in all respect of the following capacity. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR			
	2.00	cooling capacity 40 Ltr./Hr. and storage capacity 80 Ltrs	57859.00	EACH	115718.00
105		Providing & Fixing of Vertical(BEE 5 star rated) / Horizontal(BEE 3 star rated) storage water heater with outer casing made of Engineering Plastic sheet (Upto 25 Ltr) / Metal rust proof Body (35 & 50 Ltr), Glass - line / Titanium Enamel coated Pressure Pump Compatible 8 bar pressure Inner tank, Glass Line Coated , mineral filled heating element, stem type, snap action adjustable thermostat , Dual indicating lamps Injected PUF insulation, Multi Function Valve etc. as required held in position with 2/4 no. 10/12 mm anchor Fastener, duly wired with 3 core 2.5/4.0 Sqmm PVC insulated & sheathed copper conductor and 16 A/25A three pin plug top with Portable Residual Current Device (PRCD) , including making inlet, outlet Flexible alloy connection, testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			
	2.00	50 Ltr.	16565.00	EACH	33130.00
106		Wiring of light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III)			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, round tiles, 1.2 mm thick Hot Dipped Galvanized Modular Box with earth terminal, 6A Modular switch, Modular face plate with grid plate, 3 pin ceiling rose / Holder / 3 way connector, screws, making connections, testing etc. as required.			
	30.00	Short point (up to 3 mtr.)	291.00	P. point	8730.00
	70.00	Medium point (up to 6 mtr.)	209.00	P. point	14630.00
	70.00	Long point (up to 10 mtr.)	699.00	P. point	48930.00
107		Wiring of twin control light point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III) PVC conduit & it's ISI marked (IS:3419-1988) accessories, round tiles, 2 Nos Hot Dipped Galvanized M.S Modular box of 1.2 mm thick with earth terminal, 2 Nos 6 A two way Modular switch, 3 pin ceiling rose / holder / 3 way connector, Modular face plate with grid plate, screws, making connections, testing etc. as required.			
	4.00	Long point (up to 10 mtr.)	1395.00	P. point	5580.00
108		Wiring of 3/5 pin 6 amp. Light plug point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III) PVC conduit & it's ISI marked (IS:3419-1988) accessories, Hot Dipped Galvanized Modular box of 1.2 mm thick with earth terminal, 6 A modular switch, 3/5 pin 6 A modular socket, Modular face plate with grid plate, screws, making connections, testing etc. as required.			
	10.00	On board	324.00	P. point	3240.00
	10.00	Long point (up to 10 mtr..)	875.00	P. point	8750.00
109		S&F following sizes (dia.) of ISI marked virgin material MMS (IS:9537 P - III) PVC conduit along with ISI marked (IS:3419-1988) accessories as required in recess including			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		cutting the wall, covering conduit and making good the same as required.			
	100.00	20 mm	33.00	R. mtr.	3300.00
	400.00	25 mm	47.00	R. mtr.	18800.00
	100.00	32 mm	70.00	R. mtr.	7000.00
110		Supplying and drawing FR PVC insulated & unsheathed flexible copper conductor as per PWD specification for electrical Works with ISI marked (IS:694) and as per IS 8130 : 2013 of 1.1 kV grade . Wire should be made from 99.90 % purity copper, class 5 stranding in acc. to IS:8130/IEC 60228 for lower watt loss , oxygen free for less chances of oxidization, insulation PVC type A/C/D , flame retardant as per IS 10810-53, better amperage rating as per IS:3961 part 5, in existing surface or recessed PVC/ MS conduit/casing capping making connections with Copper Lugs of suitable size, Ferrules,testing etc. as required.			
	200.00	3x 1.5 sq.mm	64.00	Mtr.	12800.00
	450.00	2 x 2.5 sq. mm. + 1x1.5sqmm	90.00	Mtr.	40500.00
	100.00	4 x 10.0 sq.mm	505.00	Mtr.	50500.00
	100.00	1 x 6.0 sq.mm	75.00	Mtr.	7500.00
111		S&F following sizes of ISI marked (IS:14927 P - II) virgin material UPVC trunking along with accessories like coupler, inner, outer, elbow, square box, tee, end cap etc. on surface with screws, expansion fasteners as required.			
	50.00	32 mm x 12 mm	45.00	Mtr.	2250.00
	50.00	100 mm x 50 mm	816.00	Mtr.	40800.00
112		Supplying and drawing PE Insulated & PVC Sheathed unarmoured telephone cable with 0.5 mm dia. Solid Annealed electrolytic grade bare Copper Conductor as per IS: 8130/84 &confirming to TEC specification GR / WIR/06-03 March 2002 in existing surface or recessed conduit/casing capping. including ferruling on each pair for Identification etc. as required.			
	30.00	4 pair	30.00	Mtr.	900.00
113	7.00	P & F 1.2mm thick M.S. Recessed concealed box, round of size 150 mm dia, depth 100mm, Complete as per required.	95.00	Each	665.00
114		Providing & Fixing of 240/415 V AC MCB with positive isolation of 10 kA breaking capacity (B/ C/D tripping characteristic as per type of load and site requirement) 4 KV impulse withstand voltage, ISI marked IS 8828(1996) / conforming to IEC 60898-1 2002, IEC 60947-2, low watt			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		losses, trip free mechanism , energy limiting of class 3 as per IEC, minimum phase termination capacity of 35sq.mm. , conductor line load reversibility , IP 20 contact protection and fitted in existing distribution board/sheets, minimum electrical operation 20,000 upto 20 A rating and 10,000 upto 63 A, 5000 for 80 A & above rating including making connections, testing etc. as required.			
		Single pole MCB (With B/C curve tripping Characteristics)			
	18.00	6 A to 32 A rating	169.00	Each	3042.00
		Double pole MCB(With B/C curve tripping Characteristics)			
	2.00	40 A rating	899.00	Each	1798.00
		Four pole MCB (With B/C curve tripping Characteristics)			
	2.00	50/63 A rating	1737.00	Each	3474.00
115		Providing & Fixing of Recessed/surface mounting heavy duty horizontal type Double Door (Metal / Glazed)Distribution board with Metal end box made out from Galvanized steel / CRCA sheet not less than 1.2 mm thick conforming to IS-8623-1 & 3 / IEC 61439- 1 & 3, powder painted complete with reversible door (for double door DB only)100 amp. insulated copper bus bar/shorting link , copper neutral link, copper earth link , color coded interconnecting wire set of suitable rating and din bar,masking sheet, making internal DB terminations with copper lugs, Ferrules, detachable gland plate, including making connections, testing etc. as required.			
		Metal door (Three phase) IK-09 and IP-43 with Metal end box			
	1.00	8 Way(8+24)	4784.00	Each	4784.00
116		P&F metal clad / Plastic industrial plug top & socket unit with pin and sleeve type contact on porcelain/ bakelite base in Recessed/surface mounting heavy duty Enclosure made out from Galvanized steel / CRCA sheet not less than 1.2 mm thick conforming to IS-8623-1 & 3 / IEC 61439- 1 & 3. powder painted (without MCB) including making connections, testing etc.as required			
	2.00	20 amp, 2 pin + earth, 2 Module	1570.00	Each	3140.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

117		Providing & Fixing of 240/415 V Residual current circuit breaker (RCCB) conforming to (IS:12640-1)/ IEC 61008 -1 , rated 4 KV impulse withstand voltage truly current operated and shall operate on CBCT mechanism, provision for pad lock, min. operation 10,000 upto 63 A rating and 5000 for 100 A rating and minimum phase termination capacity of 35 sq.mm. rigid wire , IP 20 contact protection with existing distribution board / sheet including making connections, testing etc. as required.			
		Two pole 100/300mA sensitivity			
	3.00	63 A rating	2723.00	Each	8169.00
118		Providing & Fixing of following modular accessories as per PWD specification for electrical Works, made out of unbreakable and fire retardant virgin poly carbonate with brass terminals and captive screws & silver alloy contact tip with IP-20 rating , including all as per pre approved by Engineer in charge,making connections, testing etc. as required.			
	1.00	RJ-11 telephone jack single line	76.00	Each	76.00
	10.00	Blanking plate	17.00	Each	170.00
119	1.00	Providing & Fixing of ding dong/musical chime bell as per PWD specification for electrical Works, including making connection testing etc. as required.	318.00	Each	318.00
120		Providing & Fixing of modular type 120 W Step Fan regulator duly ISI marked (IS 11037:1984) with CM/L no. printed made out of unbreakable and fire retardant virgin poly carbonate with brass terminals and captive screws & silver alloy contact tip with IP-20 rating , including all as per pre approved by Engineer in charge,making connections, testing etc. as required.			
	4.00	5 step fan regulator 2 Module 360 degree rotating	328.00	Each	1312.00
121		Providing & Fixing of following size mounting grid plates with cover plates made from fire retardant UV established high performance engineering plastic suitable for all universal metal boxes for front installation & removal direct fit type complete in all respect.			
	5.00	1/2 Module	62.00	Each	310.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

122	10.00	Supplying and fixing of power plug point with Modular accessories as per PWD specification for electrical Works, on hot dipped galvanized modular box of 1.2 mm thick with earthing terminal/connector on surface or in recessed with suitable size of modular face plate with grid plate and cover plate including cost of ISI marked modular 16 amp. Switch (IS :3854) and 6/16 amp. socket outlet (IS:1293) making connection , testing , etc. as required.	460.00	Each	4600.00
123		Providing & Fixing of Wiring Accessories OEM fabricated following size GI box of 1.2 mm thick with earthing terminal and adjustable floating clamp in recess/ surface suitable for modular accessories as required.			
	10.00	1-2 Module	75.00	Each	750.00
124		Providing & Laying XLPE insulated & P.V.C. sheathed Armoured Aluminium cable confirming to IS:1554 P-I / IS :7098 P - I of 1.1 KV with H4- Grade electrolytic aluminium conductor confirming to IS 8130 of purity >99.6 %, round / flat strip armouring of cables, Inner / outer sheath confirming to IS:5831 in existing RCC / Hume / Stoneware / PVC pipe/ open duct/cable trench / Cable tray(with cable tie) including testing etc. as required of following size.			
		10.0 Sq. mm			
	70.00	4 core	179.00	Mtr	12530.00
		70.0 Sq. mm			
	250.00	3.5 core	81.00	Mtr	20250.00
125		Supply and installation of high tensile low carbon steel rod molecularly bonded with 99.9 % Copper thickness (250 microns) and confirming to UL 467, IS/IEC 62561-2 of following size and length and as per point mentioned (a), (b), [c), (d), (e) below :-			
		(a) Bore a hole of dia. 100 mm of required length, Place the rod in the centre of Hole			
		(b) filled with anti corrosive conductive compounds with the permanent sealings at both the ends, CPRI/ ERDA tested with RMS capacity of minimum 30 KA for withstanding 1 second .To ensure the moisture content and electrical conductivity, 25 kg for 2000 mm & 50 Kgs for 3000mm of resistance lowering earth enhancement material shall be used as a backfill compound. The compound shall be tested form NABL acredated lab for low resistivity (less than 0.12 Ohm - meter) & high conductivity in nature with carbon as a major content as per reference of IS 3043-1987,IEEE 80-2013 (clause			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		14.5d) , IEEE 837 & IER 1956 with latest amendemnts			
		© Connect the rod with copper Strip/Conductor/Wire with suitable clamp made from tinned copper and SS 304 Bolt			
		(d) Place Heavy duty weather proof poly-propylene earth pit chamber with lockable Jam free lid suitable for safe working load 5000 Kg or more of size Top Dia. 225 to 260 mm, Bottom Dia 300 to 350 mm. and Height 250 to 300 mm.			
		(d) Testing of earth resistance for value of 5 ohms or less as required & must record by engineer in charge during site visit and ensure to enter in measurment book.			
	4.00	25 mm thick and 3 Mtr. Long	8428.00	Set	33712.00
126		Supply & Laying following size earth strip in horizontal or vertical run in surface by means of Earth strip DMC Insulator including riveting/ soldering/ welding, Jointing shall be done by overlapping and with 2 set of Brass (for Cu strip) / GI (for GI Strip) nut bolt & spring washer spaced at 50cm making connection etc. as required.			
	50.00	25mm x 3mm G.I Hit Deep Strip	158.00	Mtr.	7900.00
127		Supply & Laying following size earth wire in horizontal or vertical run in ground/surface/recess including riveting, soldering, saddles, making connection with GI/Cu purity purity >95% thimble etc. as required. All as per pre approved by Engineer in charge.			
	50.00	8 SWG G.I. (Hot Dipped) Wire	32.00	Mtr.	1600.00
128		Providing & Fixing of BEE Star rated copper wounded double ball bearing capacitor start, aluminium body & Metallic blade ceiling fan Conforming to all the performance requirements laid down in IS 374:2019 including all amendments, as applicable ; & Carry BIS licensing (i.e. ISI marking) with down rod up to 80 cm with secondary support safety cable (steel rope) , cotter pin with 3 x 1.5 sq.mm pvc insulated flexible copper conductor making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			
	4.00	1200 mm Sweep BEE 3 Star rated (service value >=5.0 to< 5.5)	2003.00	Each	8012.00
129		P & F of Gravity Louver shutter of superior quality made out of frame of 18 swg M.S. sheet & Louvers made from 24 swg MS Sheet with enamel paint including cost of nuts, bolts, etc as			

Signature valid

Digitally signed by Rajkesh Meena
Designation : Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		reqd. All as per pre approved by Engineer in charge.			
	5.00	Up to 380 mm size	286.00	Each	1430.00
130		Making of hole in wall (brick/stone) of required and placing NP-2 RCC pipe ring of required size for housing exhaust fan and making good the same, with cement plaster required of following size. All as per pre approved by Engineer in charge.			
	5.00	Up to 457 mm size	319.00	Each	1595.00
131		Providing & Fixing of Heavy duty capacitor start, copper wound Double ball bearing 900/1400 RPM single phase Exhaust fan conforming to IS:2312 ISI marked in existing opening including making connections testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work, refer Annexure "A" attached with this BSR.			
	4.00	450 mm sweep(900/1400 RPM)	4744.00	Each	18976.00
132		Providing & Fixing of IP20 SMD Mid Power LED batten type integrated light fixture made from Powder coated Extruded aluminium housing with in built driver, System lumen efficacy ≥ 110 lm/Watt output, internal surge protection of 2.5 KV with Short & Open circuit protection, THD < 10%, P. F. ≥ 0.95 , CRI > 80, life time of minimum 50000 Burning Hours with, 70% of initial Lumen maintained till life ends, CCT 3000°K / 4000°K / 5700°K / 6000°K/6500°K (As per ANSI Bin), as required.			
	7.00	1170mm(+/-10%) LED batten with min. lumen output 2200 lm	396.00	Each	2772.00
133		Providing & Fixing of IP-20 LED Recessed / Surface Mounted, Round / Square SMD Mid Power LED Downlight with power coated die-cast aluminum housing with UV Stabilized non yellowish Diffuser with BIS compliance 2.5 KV surge protected Isolated driver, with Short & Open circuit protection, having efficiency > 85%. System Lumen efficacy of ≥ 110 lm / watt, THD < 10%, Pf. ≥ 0.95 , CRI > 80, life time of minimum 50000 Burning Hours with, 70% of initial Lumen maintained till life ends, CCT 3000°K / 4000°K / 5700°K / 6000°K/6500°K (As per ANSI Bin), maximum power consumption should not more than the specified rating and Fixture shall be of BIS standard and trade mark certificate (T.C.). Manufactures Word Mark/ Name Engraved/ Embossing/ Screen printing on housing.			
		Surface Mounting (with extruded alum. Housing			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		)			
	46.00	Minimum lumen output 1300 lm	909.00	Each	41814.00
134		Supply and erection of Galvanized Iron pole with galvanizing done in single dipping (Average coating thickness Minimum 65 Microns) continuously tapered poles having Octagonal / Circular cross-sections designed to withstand the maximum wind speed as per IS 875, The pole shaft shall be made from sheet steel (HT Steel Conforming to grade S355JO) and conforming to BSEN 10025 and shall be continuously tapered with single longitudinal welding. There shall not be any circumferential welding. The welding of pole shaft shall be done by Submerged Arc Welding (SAW) process. pole shafts shall be provided with the rigid flange plate of suitable thickness (Fe 410 conforming to IS 226 / IS 2062) with provision for fixing 4 no. foundation bolts, This base plate shall be fillet welded to the pole shaft at two locations i.e. from inside and outside. The octagonal Poles shall have lockable door of approximate 500 mm length at the elevation of 500 mm from the Base plate with bakelite sheet having 6A SP MCB and 16 sqmm stud type connector (4 nos) inside the pole at door opening for cable connection of following length and dimension as per table P-01 with base plate and foundation bolt on the Existing cement concrete foundation			
		Poles with Octagonal Cross Section			
	4.00	4 Mtr.	6414.00	each	25656.00
135		Supply and Fixing of Pole OEM fabricated hot dipped galvanised M.S. Overhang (48.3 X 3.25 mm) with cap (400 x 88.9 / 114.3 x 3.25 mm) over the existing poles.			
	4.00	Single arm overhang	1504.00	each	6016.00
136		Providing & Fixing of IK08, IP 66 protected LED Street Light Luminaire on existing bracket/pole. Fixture made of powder coated single piece pressure die cast aluminum material with heat dissipation fins on housing with UV stabilized PC (UV stablization report submitted for UV cover) /Toughened Glass cover and secondary lens on each LED & should be SMD type of 3 to 5 watt each . The System efficacy >=125 lm/ wt and potted driver & has a unique BIS R number with Input Voltage AC 120 to 270 V AC with High voltage Cutoff @>=300 V AC and Auto resetting Safety , Power Factor >0.95 driver Efficiency >85% ,THD(I) <10% Humidity 10% to 90% RH Working Temp -5C to 45C . driver current <750mA. The luminaire shall be BIS			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		certified and Trade mark certified. Life Expectancy Equal or more than 50000 burning hrs with Minimum 70% lumen maintained , CRI >70 and CCT 5700K +355K Surge protection shall be min ≥ 4 KV internal and min 10 KV external inside driver compartment. driver should be Phase to phase protection of 440 V for 4 Hrs as reqd.			
	4.00	LED Street Light fixture with Minimum lumen output 4050 lm	1785.00	each	7140.00
137		Providing & Fixing of IK10 IP66 / IP67 protected Rectangular shape LED Step Luminarie made of powder coated die cast alluminium housing with UV stabalized PC diffuser. The System level Luminous efficacy ≥ 90 Lumen/W. SMD LEDs is to be used, System CRI>70, CCT: 3000/4000/6500 K. The integral electronic driver must be potted & has a unique BIS R number constant current and Internal/external surge protection device of min. 4KV(L-N) and efficiency > 85%, PF>0.9, THD<10% and input Voltage range of 140-270V AC at 50Hz. System life of 50000 Burning hours with 70% of Initial Lumens maintained . driver current <750mA .			
	70.00	Minimum lumen output 450 lm Step light	2261.00	each	158270.00
138		SITC of IP-42 and general construction confirming to IS:8623 : 1993, wall/ free standing floor mounted dust and vermin proof compartmentalised cubical panel as specifications and Other parameters required as per point (a) ,(b), (c),(d), (e), (f), (g), (h) as below:-			
		(a)Thickness of CRCA sheet shall be 2.0 mm, cable alley compartments having concealed hinged type doors with key type lock with / without detachable extension type structure. Removable 3 mm. thick sheet steel gland plates with appropriate size of knockouts for cables shall be provided			
		(b)complete panel shall undergo a process of degreasing, Water rinsing, Activation, derusting, pickling in acid bath, phosphatising & shall be subjected to nine tank process and then Powder coated with approved shade of minimum 70 microns on both side of panel. The panel having PE foam/ Neoprene rubber gasket of not less than 3mm thickness ,required hardware , concealed hinged door with key type locking arrangement for equipment/switchgear earthed with 2.5 sq.mm braided copper wire.			
		[c] Interconnection between bus bar and switchgears /cable shall be rigidly supported and			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		made out by flexible copper wires (up to 63 amp) and by solid bus bar (>63 amp) . control wiring will be carried out with 1.5 Sq.mm, Earth wire with 2.5 Sq.mm and CT with 2.5 sq.mm flexible copper wire only. All joints / interconnections of copper bus bar shall be dully tinned . Clearance between main bus bar and risers / metal parts shall be at least 10 mm additional to width of bus bar Bus bar is insulated by Heat Shrinkable sleeves . Earth and Neutral bus bar shall be half of the size of phase bus bar. (Cost of Bus bar / Flexible wire for Interconnection between Main busbar and Switchgear is to be Paid Extra)			
		(d)Wiring between components within switchgear and Incoming / outgoing cable shall be done through the terminal block only. Direct connection shall not be permitted. Each terminal block shall be one piece moulded, barrier type, 650 volt grade, complete with washers, heads, studs with two nuts and identification strips and shall have adequate continuous current rating. For tap-offs, adjacent terminals with shorting strips shall be used. 10% Spare terminal blocks shall be provided. Wire identification on marking strip shall correspond to the designation of the wiring diagrams. All wire terminals on the equipment shall also be marked with designation corresponding to those of the wiring diagram.			
		(e)All wiring shall be enclosed in plastic channels and neatly bunched and closed in metering chamber, Wiring between terminals of various devices shall be 'point to point' (no wire splitting or tee connections) with wires neatly trucked along the back of the panels, adequately supported to prevent sagging.			
		(f)Floor mounted panel shall be mounted on Base frame of ISMC channel size 100 x 50 x 5 mm (to be paid Extra)			
		(g) Tests: The insulation resistance (with 1000 V Megger) and High voltage Power frequency test (by applying a voltage of 2.5KV for one minute) shall be measured between phases, between phase and neutral and between phase and earth. both before and after high voltage power frequency test. The insulation resistance shall not be less than three megaohm. CT Secondary current injection test shall also be carried out.			
	7.00	(h) only outer surface area on all sides shall be measured & panel to be fabricated only from CPRI approved fabricator only (CPRI Test certificates to be submitted)	5575.00	Sqmtr	39025.00
139		Supplying and fixing of Aluminium (IEC 60105			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		ISO 209-1,2) / Copper (IEC 60028) bus bar by means of SMC / DMC type insulator with standard short circuit withstand capacity , high tensile nuts and bolts spring washers in existing panel including bending , cutting in required shape and size and colour coding with heat shrinkable PVC sleeves.			
	10.00	Electrolytic grade Aluminium bus bar 6010 grade	559.00	Kg	5590.00
140		Providing & Fixing of IS: 13875 & IEC :61326 confirming LED Digital type (up to 500) V range Volt meter / Direct- Ammeter / CT oertated ammeter/ Frequency meter / KWH meter / Multi Function Meter / Power analyzer of class 1 accuracy as per IS : 1248 of size 96mm x 96 mm including making connection by PVC insulated copper conductor with PVC sleeves / channel etc. as required.			
	1.00	Three phase Ammeter with inbuilt sepector switch	1506.00	Each	1506.00
	1.00	Three phase Voltmeter with inbuilt sepector switch	1506.00	Each	1506.00
	1.00	Three phase AMP + HZ + PF + KW + KVA + KVAR + KVARH+KWH+DUAL ENERGY+ ENERGY+THD-I, THD-V & RUN HRS	4746.00	Each	4746.00
141		Providing & Fixing of BIS approved Current Transformer as per PWD specification for electrical Works ,ISI marked as per IS 2705-1992/ conforming to IEC 60044-1, with secondary terminal of CT shall be brought out suitable to a terminal block which shall be easier accessible for testing and terminal connection , with all necessary support in existing panel including connection etc. as required Current transformer Ring Type Tape Wound/Resin Cast Wound as per IS 16227 with, Accuracy Cl, CT ratio and burden as specified. ISF<=5, Cu cross section of secondary wire 1.5sqmm (minimum), including all necessary support in existing panel including connection etc. as required .			
		Ring type tape wound CT			
	3.00	C T Class I, Ratio upto 150/5, Burden 5 VA	647.00	Each	1941.00
142		Providing & Fixing of 110/220 V, unibody LED Indicating lamp IEC 60947 with integral circuit, IP 65 above panel & IP 20 terminal block, Approx. body dia for panel not less then 20 mm, length min. 50mm, front LED cover dia min. 29 mm, contact material phosphor bronze for Led, PCB contacts shall be of brass (tin plated), impulse dielectric tested for 2.5 KV, Rated insulation resistance shall be 100 M ohm at 500VDC including connection etc. as required.			
	3.00	Red/yellow/Green colour	147.00	Each	441.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

	3.00	Blue / white Colour	232.00	Each	696.00
143		SITC of 3 /4 pole current limiting Moulded case circuit breaker (MCCB) made of flame retardent & heat resistant material having following current rating, short circuit breaking capacity at 440/415 V, 50 Hz; O/L & S/C settings , conforming to IS/IEC 60947 P -2 :2003 with front face and centralised adjustable, trip free mechanisum, true contact position indicator, line load interchangeability, designed for both horizontal & vertical mounting without any adverse effect on electrical performance, suitable for operation upto 55 degree and without derating upto 40 degree, pollution degree 3, having positive isolation capability, push (test) to trip, trip time less then 10 ms under s/c condition, Breaking capacity Ics = 100% Icu. U imp =8 KV, rated insulation voltage 690 V. provision for UVR , shunt trip , earth fault trip, door interlock, pad lock & rotary handle , including making connections etc. as required.			
		4 pole MCCB With Thermal Magnetic release			
	2.00	up to 100 Amp , 25 kA, adjustable O/L & adjustable S/C setting,	6219.00	each	12438.00
144		Providing & Fixing of IK08 IP-66 protected high power LED flood light system with single piece Pressure diecast aluminium housing, toughened glass diffuser with suitable lenses on LED to achieve various beam angles, of high power LED of 3 to 5 watt each . Integrated potted driver as a unique BIS R number having efficiency more than 85 % and in compliance to BIS certified and Trade mark certificate. The System level Luminaire efficacy >=125 lm/ wt. LED driver Input Voltage AC 120 to 270 V AC with High voltage Cutoff @>=300 V AC and Auto resetting Safety .Power Factor >0.95 , THD(I) <10% , driver current <=750mA. driver should be Phase to phase protection of 440 V for 4 Hrs. Electrical Connector , Surge Protection Min >=4KV internal and 10KV external but inside driver compartment, System life of 50000 Burning hours with 70% of Initial Lumens maintained, CRI>70 and CCT 5700K ±355K. Manufactures Word Mark/Name Engraved/Embossing/Screen printing on die cast housing to allow traceability/authenticity. Fixture shall be IS 10322 Comlianced.OEM Must have its own in house NABL lab setup for all testing facilities for LED fixtures. (LM79/LM80) Certificate/ report with liable warranty of product/accessories from OEM shall be submitted. All as per pre approved by			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			
	30.00	High Power LED Flood Light Minimum lumen output 8700 lm	3739.00	Each	112170.00
		Basketball Court			
1	600.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead upto 50mtr. and lift upto 1.5Mtr.	9.00	sqm	5400.00
2	90.00	Carriage of Material: Earth, Sand, Lime, Morrum manure or sludge	80.00	cum	7200.00
3	600.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	5.00	sqm	3000.00
4	60.00	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils.	178.00	Cum	10680.00
5		Construction of Embankment with Material Obtained from Borrow Pits			
	90.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300-1 and 300-2 with a lead upto 1000 m as per MoRTH Specification Clause 305.3	58.00	Cum	5220.00
6		Granular Sub-base with Well Graded Material (Table 400-1)			
		By Mix in Place Method			
		Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor Mount Grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per MoRTH Specification Clause 401.			
	90.00	For Grading I Material	512.00	Cum	46080.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

7		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
	396.90	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	3302.00	Cum	1310563.80
8	396.90	Providing and laying M30 grade controlled cement concrete pavements including mixing and vibrations concrete with necessary needle vibrators and surface with screed board vibrating complete in all respect with 20/25 mm stone aggregate (crusher broken) including anti-skid textured finish to required camber/ super lavation and grade including curing etc. as per specification with cement concrete M-30 grade including cost of Steel frame work for sides of C.C. pavement consisting of M. S. channels flats and angles with required steel pegs (some of them may left embedded in concrete/ including providing frame work	5514.00	Cum	2188506.60
i	2646.00	Extra for vacuum processed concrete including cost of equipments labour etc.	101.00	Sqm	267246.00
ii	1653.00	Cutting of construction joint/ longitudinal joint 4 to 6 mm. wide using mechanical concrete cutter including cost of diamond bit cutting wheel and filling of bitumen sealing compound in groove including cost of sealing compound. 75 mm depth	140.00	Mtr	231420.00
14		Providing and laying of paver block as per IS 15658 : 2006 (Indian standard for precast concrete block for paving- specification) and IRC : SP:63-2004 (guidelines for the use of interlocking concrete block pavement)			
		M-30, 60 mm thick to be used in non traffic areas like building premises, monument premises, land scapes, public gardens/ park, domestic drives, paths and patios, Embankment slopes, sand stabilization Area etc.(As per table 1 of IS 15658:2006			
	309.00	Category 'B' Denated only two side like I,Z,T shape etc. as per IRC SP 63:2004	786.00	Sqm	242874.00
		Volleyball Court			
1	1000.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50 Mtr. and lift up to 1.5 Mtr.: (Selected area) All kinds of soil	9.00	Sqm	9000.00
2	100.00	Carriage of Material: Earth, Sand, Lime, Morrum manure or sludge	5.00	Sqm	12500.00
3	1000.00	Clearing jungle including uprooting of rank	5.00	Sqm	12500.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.			
4		Construction of Embankment with Material Obtained from Borrow Pits			
	36.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300-1 and 300-2 with a lead upto 1000 m as per MoRTH Specification Clause 305.3	127.00	Cum	4572.00
5		Water Bound Macadam Sub-base/base with Stone Screening			
		WBM Grading 1			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening & binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per MoRTH Specification Clause 404.			
		Using Crusher Broken Aggregate			
	96.90	By Mechanical Means	1016.00	Cum	98450.40
		WBM Grading 2			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per MoRTH Specification Clause 404. using Crusher borken aggregate			
	96.90	By Mechanical Means	1093.00	Cum	105911.70
		Construction of Tubewell Work in Stadium			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

1		Construction of tube-well from ground levels and upto 100 Meter depth and above to accommodate housing and assembly pipe of following sizes in all types of alluvium strata by percussion/ rotary drilling method and with gravel as per IS:4097-1967 and packing as per IS:2800 (Part I -& II) 1979 as amended upto date (the work includes the cost of gravel & its primary packing and packing during development, lowering of housing & strainer assembly pipes, with supply and wrapping of coir-rope, wherever necessary, for arresting fine sand particles. The work will not include cost of housing pipe and strainer pipe assembly and development work, but work would be completed after obtaining sand free water).			
1.1	500.00	200mm –do-.	1464.00	R Mtr.	732000.00
2	2.00	Testing verticality of tube-well by plumbing system and yield test and draw down test by pumping system as per IS: 2800 (Part II) 1979.	8385.00	each	16770.00
3	60.00	Development of tube well as per IS specification using suitable compressor to give sand free water for required yield of the gravel packed tube well.	600.00	Hr.	36000.00
4		Supply of ERW M.S. black casing pipe ISI marked (IS:4270/1992) of grade Fe410 of following sizes at site of work.			
4.1	200.00	Nominal bore of pipe: 100mm . Out side dia of pipe : 114.3 thick ness of pipe : 5.0mm .	1728.00	Mtr.	345600.00
5		Supply of strainer pipes made of ERW M.S. black pipe ISI mark of following sizes at the site of work including required size of slotting as per IS:8110-1985.			
5.1	50.00	200mm–do-.	2031.00	Mtr.	101550.00
6		S & F tube well cover of M.S.sheet (6mm thick) with nuts and bolts complete for casing size:			
6.1	2.00	200mm dia	373.00	Each	746.00
7		Providing & lowering of G.I. Pipes, flange pipe including rubber washer and nuts of 8 mm dia complete in all respect I.S.1239 Marked.			
7.1	480.00	B Class 50 mm dia	498.00	R. Mtr.	239040.00
8	40.00	Supplying and fixing C.I. Cover with frame, C.I. gratings for chambers & man holes.	72.00	kg	2880.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

9		SITC of Radial / mixed flow ISI marked water and anti-corrosive liquid filled submersible motor pump sets suitable for 100/150mm dia borewell. The size of adopter fixed on top of the motor should exceed the top of coupler , for safeguard the coupler. The construction material of motor and pump should match IS: 8034 : 2018 and IS: 9283 guideline. The radial flow pumpset should operate at 5 star energy efficiency level of BEE and mixed flow pump set should operate at 3 star energy level of BEE, accompanied by valid BEE certificate. Motor should be IE2 class as per IEC 60034-2-1: 2007, IEC 60034-30: 2008, & IS12615:2011 with required accessories including making connection suitable for Bore well. The job includes labour part of lowering of riser pipe G.I./ H.D.P.E. with rope, cables & pump, installation of complete fitting and accessories, jointing of electrical cables up to Starter. All labour for testing of submersible pumps set and supply of water to water mains, complete in all respect. OEM shall have submit NABL / CPRI / ERDA accredited lab type test certificate before execution. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			
9.1		150 mm diameter Submersible pump shall have following HP Rating, phase, Head range, Discharge range respectively.			
9.1.1	2.00	5.0 HP, 3-Ø, (68 - 102)Mtr, (225-85) LPM	53024.00	Each	106048.00
10		P/Laying ISI marked P.V.C. insulated submersible cable confirming to(IS:694) and as per IS 8130 : 2013 of 1.1 kV grade . Wire should be made from 99.90 % purity copper, stranding in acc. to IS:8130/IEC 60228 for lower watt loss , oxygen free for less chances of oxidization, insulation PVC type A/C/D , flame retardant as per IS 10810-53, better amperage rating as per IS:3961 part 5, existing pipe / open trench / Cable tray / on surface including making connection etc. as required. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR			
10.1	700.00	6.0 Sq.mm 3 core flat / Round	300.00	MTR	210000.00
11		SITC of Contactor OEM Fabricated DOL/Star-Delta Starter panel with switchgear selection as per Type-2 Cordinatiom Chart and made out from 1.6 mm thick powder coated CRCA sheet, enclosure comprising of over load protection relay, short circuit & single phasing protection,			

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		Illuminated ON / OFF push buttons, ammeter, voltmeter, indicating lamps etc. suitable for following rating motors complete in all respect. All as per pre approved by Engineer in charge. For additional technical parameters of products/work, refer Annexure "A" attached with this BSR.			
11.1	2.00	3.0 HP to 5.0 HP (DOL starter)	10173.00	Each	20346.00
		Kho-Kho Ground			
1	840.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50 Mtr. and lift up to 1.5 Mtr.: (Selected area) All kinds of soil	9.00	Sqm	7560.00
2	84.00	Carriage of Material: Earth, Sand, Lime, Morrum manure or sludge	80.00	Sqm	6720.00
3	840.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	5.00	Sqm	4200.00
4	253.13	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils.	178.00	cum	45056.25
5		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
	3.02	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	3302.00	cum	9955.53
6		Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in:			
	9.07	Cement Sand Mortar 1:6 (1-Cement:6-Sand).	2838.00	cum	25733.57
7	43.20	Providing & fixing precast cement concrete coping 1 : 2 : 4 mix 50mm thick complete as per specification :	367.00	Sqm	15854.40
8	86.40	Plaster on new surface on walls in cement sand mortar 1:6 including racking of joint etc. complete fine finished: 20 mm thick.	90.00	Sqm	16416.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

9		Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding:			
	86.40	New work (Two or more coats applied @ 3.84 kg/10 sqm).	53.00	sqm	4579.20
10		Construction of Embankment with Material Obtained from Borrow Pits			
i	76.50	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300-1 and 300-2 with a lead upto 1000 m as per MoRTH Specification Clause 305.3	58.00	Cum	4437.00
11		Water Bound Macadam Sub-base/base with Stone Screening			
		WBM Grading 1			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening & binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per MoRTH Specification Clause 404.			
		Using Crusher Broken Aggregate			
	51.98	By Mechanical Means	1016.00	Cum	52806.60
		WBM Grading 2			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per MoRTH Specification Clause 404. using Crusher borken aggregate			
	51.98	By Mechanical Means	1093.00	Cum	56808.68
		Kabaddi Ground-2			
1	1500.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50 Mtr. and lift up to 1.5 Mtr.: (Selected area) All kinds of soil	9.00	Sqm	13500.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 17:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

2	150.00	Carriage of Material: Earth, Sand, Lime, Morrum manure or sludge	80.00	Sqm	12000.00
3	1500.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	5.00	Sqm	7500.00
4	438.75	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils.	178.00	cum	78097.50
5		Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.			
	4.05	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	3302.00	cum	13373.10
6		Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in:			
	12.60	Cement Sand Mortar 1:6 (1-Cement:6-Sand).	2838.00	cum	35758.80
7	54.00	Providing & fixing precast cement concrete coping 1 : 2 : 4 mix 50mm thick complete as per specification :	367.00	Sqm	19818.00
8	108.00	Plaster on new surface on walls in cement sand mortar 1:6 including racking of joint etc. complete fine finished: 20 mm thick.	190.00	sqm	20520.00
9		Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding:			
	108.00	New work (Three or more coats).	53.00	sqm	5724.00
10		Construction of Embankment with Material Obtained from Borrow Pits			
i	132.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300-1 and 300-2 with a lead upto 1000 m as per MoRTH Specification Clause 305.3	58.00	Cum	7656.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

11		Water Bound Macadam Sub-base/base with Stone Screening			
		WBM Grading 1			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening & binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per MoRTH Specification Clause 404.			
		Using Crusher Broken Aggregate			
	47.25	By Mechanical Means	1016.00	Cum	48006.00
		WBM Grading 2			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per MoRTH Specification Clause 404. using Crusher borken aggregate			
	47.25	By Mechanical Means	1093.00	Cum	51644.25
		Handball Ground			
1	1000.00	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish lead up to 50 Mtr. and lift up to 1.5 Mtr.: (Selected area) All kinds of soil	9.00	Sqm	9000.00
2	100.00	Carriage of Material: Earth, Sand, Lime, Morrum manure or sludge	125.00	Sqm	12500.00
3	1000.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	5.00	Sqm	5000.00
4		Construction of Embankment with Material Obtained from Borrow Pits			
	36.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300-1 and 300-2 with a lead upto 1000 m as per MoRTH Specification	127.00	Cum	4572.00

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign

		Clause 305.3			
5		Water Bound Macadam Sub-base/base with Stone Screening			
		WBM Grading 1			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening & binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per MoRTH Specification Clause 404.			
		Using Crusher Broken Aggregate			
	79.20	By Mechanical Means	1016.00	Cum	80467.20
		WBM Grading 2			
		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per MoRTH Specification Clause 404. using Crusher borken aggregate			
	79.20	By Mechanical Means	1093.00	Cum	86565.60

**Secretary
Rajasthan State Sports Council
Jaipur**

Signature valid

Digitally signed by Rajkesh Meena
Designation: Secretary
Date: 2026.08.19 12:45:12 IST
Reason: Approved

RajKaj Ref No.:
24126045

M e-Sign